

Alabama Department of Transportation
Proposal Item Summary

007. ACAA61945-ATRP(013)

LIMESTONE COUNTY

Contract Time: 90 Working Days

DBE Goal Percent: 7.00

for constructing the Additional Lanes on East Limestone Road from the junction of McLemore Circle to a point near East Limestone School. Length 0.288 mi.

The Bracket Estimate on this project is from \$705,529 to \$862,314.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$11.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
204A000	1	Each	Closing Water Well
206C010	177	SQYD	Removing Concrete Driveway
206D000	540	LF	Removing Pipe
209A000	7	Each	Mailbox Reset, Single
210A000	357	CUYD	Unclassified Excavation
210D001	2,101	CUYD	Borrow Excavation (Loose Truckbed Measurement)
214A000	365	CUYD	Structure Excavation
214B001	229	CUYD	Foundation Backfill, Commercial
327A021	910	Ton	Plant Mix Bituminous Base, Mix 2
405A000	1,400	Gal	Tack Coat
407B000	1	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A360	735	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B651	441	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	612	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B681	910	Ton	Superpave Bituminous Concrete Lower Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
430B046	20	Ton	Aggregate Surfacing (Aldot #2)
430B047	65	Ton	Aggregate Surfacing (3/4" Down,Crusher Run)
530A001	65	LF	18" Roadway Pipe (Class 3 R.C.)
530A002	136	LF	24" Roadway Pipe (Class 3 R.C.)
530A003	80	LF	30" Roadway Pipe (Class 3 R.C.)
533A097	313	LF	15" Storm Sewer Pipe (Class 3 R.C.)
533A098	96	LF	18" Storm Sewer Pipe (Class 3 R.C.)
533A099	16	LF	24" Storm Sewer Pipe (Class 3 R.C.)
533A100	161	LF	30" Storm Sewer Pipe (Class 3 R.C.)
600A000	1	LS	Mobilization
610C001	14	Ton	Loose Riprap, Class 2
610D003	154	SQYD	Filter Blanket, Geotextile
618B003	145	SQYD	Concrete Driveway, 6" Thick (Includes Wire Mesh)
619A001	1	Each	15" Roadway Pipe End Treatment, Class 1
619A003	2	Each	24" Roadway Pipe End Treatment, Class 1
619A004	1	Each	30" Roadway Pipe End Treatment, Class 1
619A100	1	Each	15" Side Drain Pipe End Treatment, Class 1
619A103	2	Each	30" Side Drain Pipe End Treatment, Class 1
621A011	2	Each	Junction Boxes, Type 1 Or 1P
621B011	2	Each	Junction Box Units, Type 1 Or 1P

Item No.	Quantity	Units	Description
621C002	3	Each	Inlets, Type C, P1 Or P3
621C015	7	Each	Inlets, Type S1 Or S3 (1 Wing)
621C017	2	Each	Inlets, Type S1 Or S3 (2 Wing)
621D015	2	Each	Inlet Units, Type S1 Or S3
623A001	294	LF	Concrete Gutter (Valley)
623C000	2,303	LF	Combination Curb & Gutter, Type C
650A000	488	CUYD	Topsoil
652A100	1	Acre	Seeding
654A000	912	SQYD	Solid Sodding
656A010	1	Acre	Mulching
665A000	1	Acre	Temporary Seeding
665B001	3	Ton	Temporary Mulching
665G000	260	Each	Sand Bags
665J002	2,474	LF	Silt Fence
665O001	2,474	LF	Silt Fence Removal
665Q002	200	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 50,000.00)
701E000	2,392	LF	Solid Temporary Traffic Stripe
701E010	1,672	LF	Broken Temporary Traffic Stripe
701G249	110	LF	Solid White, Class 2, Type A Traffic Stripe
701G258	1,672	LF	Broken Yellow, Class 2, Type A Traffic Stripe
701G263	2,392	LF	Solid Yellow, Class 2, Type A Traffic Stripe
703A002	218	SQFT	Traffic Control Markings, Class 2, Type A
703B002	137	SQFT	Traffic Control Legends, Class 2, Type A
703D001	218	SQFT	Temporary Traffic Control Markings
705A030	5	Each	Pavement Markers, Class A-H, Type 2-C
705A032	82	Each	Pavement Markers, Class A-H, Type 1-B
705A037	22	Each	Pavement Markers, Class A-H, Type 2-D
705A038	35	Each	Pavement Markers, Class A-H, Type 2-E
730Y000	1	LS	Furnishing And Installing Pedestal Pole And Foundation With Flashing Beacon
730Y040	1	LS	Removal Of Pedestal Pole And Foundation With Flashing Beacon
740B000	340	SQFT	Construction Signs
740D000	60	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone