

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**018. ACBRZ60414-ATRP(011)**

**COOSA COUNTY**

Contract Time: 90 Working Days

DBE Goal Percent: 1.00

for constructing the Bridge Replacement and Approaches on CR-15 over Weogufka Creek. Length 0.132 mi.

The Bracket Estimate on this project is from \$736,120 to \$899,702.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
201A002	1 LS		Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
206A001	1 LS		Removal Of Old Bridge, Station 5+00.07
210A000	1,132 CUYD		Unclassified Excavation
231B001	197 Ton		Roadbed Stabilizing Material, ALDOT #467
301A012	1,201 SQYD		Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	1,201 SQYD		Bituminous Treatment A
405A000	33 Gal		Tack Coat
407B000	1 Mile		Joint Sealant For Hot Mix Asphalt Pavement
424A340	92 Ton		Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B636	189 Ton		Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range A/B
502A000	164 LB		Steel Reinforcement
505G003	24 Each		Pile Points (Type A, 12")
505G004	15 Each		Pile Points (Type A, 14")
505H000	713 LF		Pilot Holes
505M002	499 LF		Steel Piling Furnished And Driven (HP 12x53)
505M004	336 LF		Steel Piling Furnished And Driven (HP 14x73)
507A000	2 Each		Wire Rope Abutment Anchor Assembly
510A007	33 CUYD		Bridge Substructure Concrete
511A000	50 Each		Elastomeric Bearing Type 1
512A008	2 Each		Precast Concrete Abutment Caps, 2'-0" Wide By 1'-7" Deep By 28'-0" Long
512B003	3 Each		Precast Concrete Intermediate Bent Caps, 2'-0" Wide By 1'-7" Deep By 27'-6" Long
512C017	20 Each		Precast Concrete Type 1 Span Section, 3'-6" By 2'-0" Deep By 39'-11 3/4" Long
512C025	8 Each		Precast Concrete Type 2C Span Section, 3'-6" By 2'-0" Deep By 39'-11 3/4" Long
512D025	4 Each		Precast Concrete Barrier Rail Intermediate Section, 39'-11" Long
512D030	4 Each		Precast Concrete Barrier Rail End Section, 39'-11 3/8" Long
512E002	16 Each		Precast Concrete Abutment Panels, Type A3
512F002	8 Each		Precast Concrete Wing Panels, Type W3
512G000	4 Each		Precast Concrete Abutment Wing Cap Panels
600A000	1 LS		Mobilization
610C001	329 Ton		Loose Riprap, Class 2
610D003	260 SQYD		Filter Blanket, Geotextile
630C003	4 Each		Guardrail End Anchor, Type 13
630C080	4 Each		Guardrail End Anchor, Type 20 Series (MASH)
650A000	240 CUYD		Topsoil
652A100	1 Acre		Seeding
656A010	1 Acre		Mulching
665A000	1 Acre		Temporary Seeding
665B001	2 Ton		Temporary Mulching
665F000	140 Each		Hay Bales

Item No.	Quantity	Units	Description
665J002	1,400	LF	Silt Fence
665O001	1,400	LF	Silt Fence Removal
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 37,000.00)
701G144	320	LF	Solid White, Class W, Type A Traffic Stripe
701G152	320	LF	Solid Yellow, Class W, Type A Traffic Stripe
701G249	1,081	LF	Solid White, Class 2, Type A Traffic Stripe
701G263	1,081	LF	Solid Yellow, Class 2, Type A Traffic Stripe
705A037	18	Each	Pavement Markers, Class A-H, Type 2-D
740B000	143	SQFT	Construction Signs
740F002	8	Each	Barricades, Type III
740I002	4	Each	Warning Lights, Type B