

Alabama Department of Transportation
Proposal Item Summary

037. ST-049-000-012

MOBILE COUNTY

Contract Time: 30 Working Days

for constructing the Resurfacing, Driveway, and Parking Lots with ADA Curb Ramps at the MOWA Visitor Center.

The Bracket Estimate on this project is from \$77,481 to \$94,699.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	9 SQYD		Removing Concrete Sidewalk
206D002	22 LF		Removing Curb
405A000	526 Gal		Tack Coat
424A340	382 Ton		Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	25 Ton		Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1 LS		Mobilization
618A000	9 SQYD		Concrete Sidewalk, 4" Thick
623B000	22 LF		Concrete Curb, Type N
674A000	100 LF		Construction Safety Fence
680A001	1 LS		Geometric Controls
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 8,000.00)
701G263	580 LF		Solid Yellow, Class 2, Type A Traffic Stripe
703A000	1,038 SQFT		Traffic Control Markings, Class 1, Type A
703A002	860 SQFT		Traffic Control Markings, Class 2, Type A
703D002	860 SQFT		Temporary Traffic Control Markings (Paint)
740B000	198 SQFT		Construction Signs
740D000	10 Each		Channelizing Drums
740E000	25 Each		Cones (36 Inches High)
740M001	25 Each		Ballast For Cone