

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**024. ERPR-9010(136)**

**ESCAMBIA COUNTY**

Contract Time: 30 Working Days

for constructing the Drainage Structure Repairs on SR-41 at MP 9.100 in Brewton. Length 0.015 mi.

The Bracket Estimate on this project is from \$85,355 to \$104,322.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$10.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
201A002	1 LS		Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
206C000	12 SQYD		Removing Concrete Sidewalk
206D000	92 LF		Removing Pipe
206E000	1 Each		Removing Headwalls
210A000	18 CUYD		Unclassified Excavation
210D022	60 CUYD		Borrow Excavation (Loose Truckbed Measurement)(A-2-4(0) or A-4(0) )
214A000	100 CUYD		Structure Excavation
214B001	30 CUYD		Foundation Backfill, Commercial
305B077	100 Ton		Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	6 Gal		Tack Coat
407B000	1 Mile		Joint Sealant For Hot Mix Asphalt Pavement
424A363	5 Ton		Superpave Bituminous Concrete Wearing Surface Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	16 Ton		Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
530A002	136 LF		24" Roadway Pipe (Class 3 R.C.)
600A000	1 LS		Mobilization
602A000	8 Each		Right Of Way Markers
610C001	29 Ton		Loose Riprap, Class 2
610D003	23 SQYD		Filter Blanket, Geotextile
618A000	12 SQYD		Concrete Sidewalk, 4" Thick
619A202	2 Each		24" Roadway Pipe End Treatment, Class 1 (Double Line)
650A000	34 CUYD		Topsoil
654A001	500 SQYD		Solid Sodding (Bermuda)
665B001	3 Ton		Temporary Mulching
665E000	500 SQYD		Polyethylene
665J002	300 LF		Silt Fence
665O001	300 LF		Silt Fence Removal
665Q002	200 LF		Wattle
666A001	1 Acre		Pest Control Treatment
680A001	1 LS		Geometric Controls
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 8,000.00)
701E000	80 LF		Solid Temporary Traffic Stripe
701G253	40 LF		Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701G265	40 LF		Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
740B000	396 SQFT		Construction Signs
740D000	100 Each		Channelizing Drums
740E000	100 Each		Cones (36 Inches High)
740F002	2 Each		Barricades, Type III
740G000	2 Each		Barricades, Type I, (Portable, 24 Inches Wide)
740I002	2 Each		Warning Lights, Type B

Item No.	Quantity	Units	Description
740M001	100 Each	Ballast For Cone	