

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**026. ERPR-9010(142)**

**RUSSELL COUNTY**

Contract Time: 85 Working Days

DBE Goal Percent: 1.00

for constructing the Front Slope Repair on SR-1 (US-431) at MP 85.500 (Northbound Lane) southwest of Pittsview.

The Bracket Estimate on this project is from \$1,605,355 to \$1,962,101.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
201A002	1 LS		Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 3 Acre)
206D000	86 LF		Removing Pipe
206E000	1 Each		Removing Headwalls
210A000	9,760 CUYD		Unclassified Excavation
210D021	6,000 CUYD		Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
214A000	1,100 CUYD		Structure Excavation
214B001	360 CUYD		Foundation Backfill, Commercial
219A000	5,900 Ton		Rock Buttress For Landslide Correction
219B001	924 LF		Special Underdrain 8 Inch Diameter
219C003	2,080 SQYD		Special Filter Blanket, Geotextile
305B071	1,410 Ton		Coarse Aggregate, Section 801, For Miscellaneous Use
305B077	3,000 Ton		Crushed Aggregate, Section 825, For Miscellaneous Use
530A003	379 LF		30" Roadway Pipe (Class 3 R.C.)
600A000	1 LS		Mobilization
602A000	4 Each		Right Of Way Markers
608A000	16,000 SQYD		Separation Geotextile
610C001	15,800 Ton		Loose Riprap, Class 2
619A004	1 Each		30" Roadway Pipe End Treatment, Class 1
621A004	4 Each		Junction Boxes, Type 4
621B004	3 Each		Junction Box Units, Type 4
621C057	1 Each		Inlets, Type 1 Special
650A000	100 CUYD		Topsoil
652A100	1 Acre		Seeding
654A001	150 SQYD		Solid Sodding (Bermuda)
656A010	1 Acre		Mulching
659C002	1,100 SQYD		Erosion Control Product, Type S2
665A000	1 Acre		Temporary Seeding
665B001	3 Ton		Temporary Mulching
665J002	900 LF		Silt Fence
665N000	100 Ton		Temporary Coarse Aggregate,ALDOT Number 1
665O001	900 LF		Silt Fence Removal
665Q002	300 LF		Wattle
673A000	822 SQYD		Clay Liner
680A001	1 LS		Geometric Controls
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 133,000.00)
740B000	512 SQFT		Construction Signs
740D000	50 Each		Channelizing Drums
740E000	50 Each		Cones (36 Inches High)
740M001	50 Each		Ballast For Cone