

**Alabama Department of Transportation
Proposal Item Summary**

036. HSIP-0008(590)

DALLAS COUNTY

Contract Time: 105 Working Days

DBE Goal Percent: 3.00

for constructing the Traffic Signal Improvements (Drainage, Traffic Signals, and Traffic Stripe) on SR-8 (US-80) from the intersection of SR-219 (Landline Road) to the junction of SR-41 in Selma. Length 4.374 mi.

The Bracket Estimate on this project is from \$1,341,417 to \$1,639,509.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$30.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	95	SQYD	Removing Concrete Sidewalk
206C001	141	SQYD	Removing Concrete Pavement
206C002	14	SQYD	Removing Concrete Slope Paving
206D002	87	LF	Removing Curb
206E000	1	Each	Removing Headwalls
210A000	62	CUYD	Unclassified Excavation
210D011	146	CUYD	Borrow Excavation (A4 Or Better)
214A000	64	CUYD	Structure Excavation
214B001	19	CUYD	Foundation Backfill, Commercial
305B077	16	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
424A356	2	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424C370	5	Ton	Superpave Bituminous Concrete Base Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
430B050	50	Ton	Aggregate Surfacing(ALDOT#1)
530B070	24	LF	77" Span, 52" Rise Roadway Pipe (14 Gauge C.C.S.P.I.) (Extension)
533A857	24	LF	18" Storm Sewer Pipe
600A000	1	LS	Mobilization
610D003	110	SQYD	Filter Blanket, Geotextile
610E000	3,950	SQYD	Tied Concrete Block Mat
614A000	9	CUYD	Slope Paving
618A000	298	SQYD	Concrete Sidewalk, 4" Thick
619A002	1	Each	18" Roadway Pipe End Treatment, Class 1
619B059	1	Each	77" Span, 52" Rise Roadway Pipe End Treatment, Class 2
621C017	1	Each	Inlets, Type S1 Or S3 (2 Wing)
623A000	9	LF	Concrete Gutter
623C000	481	LF	Combination Curb & Gutter, Type C
630A001	13	LF	Steel Beam Guardrail, Class A, Type 2
630C001	1	Each	Guardrail End Anchor, Type 8
630C080	1	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	89	CUYD	Topsoil
652A100	1	Acre	Seeding
654A001	7,200	SQYD	Solid Sodding (Bermuda)
665A000	1	Acre	Temporary Seeding
665B001	1	Ton	Temporary Mulching
665F000	25	Each	Hay Bales

Item No.	Quantity	Units	Description
665G000	350	Each	Sand Bags
665J002	355	LF	Silt Fence
665O001	355	LF	Silt Fence Removal
665P005	2	Each	Inlet Protection, Stage 3 Or 4
665Q002	300	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 75,000.00)
701E001	500	LF	Solid Temporary Traffic Stripe (Paint)
701G253	600	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701H000	350	LF	Solid Traffic Stripe Removed (Paint)
703A002	5,284	SQFT	Traffic Control Markings, Class 2, Type A
703C000	475	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Paint)
703D001	190	SQFT	Temporary Traffic Control Markings
705A030	51	Each	Pavement Markers, Class A-H, Type 2-C
710A115	59	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick Or Steel Flat Sign Panels 14 Gauge (Type III Or Type IV Background)
710A126	96	SQFT	Class 8, Aluminum Flat Sign Panels 0.08" Thick Or Steel Flat Sign Panels 14 Gauge (Type IX Background)
710B021	196	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
730A000	1	LS	Removal Of Existing Traffic Control Unit (SR-8 at Summerfield Road)
730A001	1	LS	Removal Of Existing Traffic Control Unit (SR-8 at Montague Street)
730A002	1	LS	Removal Of Existing Traffic Control Unit (SR-8 at US-80)
730A012	1	LS	Removal Of Existing Traffic Control Unit (Partial) (SR-8 at Landline Road)
730A013	1	LS	Removal Of Existing Traffic Control Unit (Partial) (SR-8 at Medical Center Parkway)
730A014	1	LS	Removal Of Existing Traffic Control Unit (Partial) (SR-8 at Bell Road)
730A015	1	LS	Removal Of Existing Traffic Control Unit (Partial) (SR-8 at Franklin Street)
730A016	1	LS	Removal Of Existing Traffic Control Unit (Partial) (SR-8 at Marie Foster Street)
730A017	1	LS	Removal Of Existing Traffic Control Unit (Partial) (SR-8 at Walmart Entrance)
730C000	1	LS	Furnishing And Installing Traffic Control Unit (SR-8 at Landline Road)
730C001	1	LS	Furnishing And Installing Traffic Control Unit (SR-8 at Medical Center Parkway)
730C002	1	LS	Furnishing And Installing Traffic Control Unit (SR-8 at Bell Road)
730C003	1	LS	Furnishing And Installing Traffic Control Unit (SR-8 at Summerfield Road)
730C004	1	LS	Furnishing And Installing Traffic Control Unit (SR-8 at Montague Street)
730C005	1	LS	Furnishing And Installing Traffic Control Unit (SR-8 at Broad Street)
730C006	1	LS	Furnishing And Installing Traffic Control Unit (SR-8 at Franklin Street)
730C007	1	LS	Furnishing And Installing Traffic Control Unit (SR-8 at Marie Foster Street)
730C008	1	LS	Furnishing And Installing Traffic Control Unit (SR-8 at Walmart Entrance)
730C009	1	LS	Furnishing And Installing Traffic Control Unit (SR-8 at US-80)
730E000	12	Each	Metal Traffic Signal Pole Foundation
730F000	1	Each	Metal Traffic Signal Pole With Two (2) 55 Ft Mast Arms
730F001	1	Each	Metal Traffic Signal Pole With 60 Ft Mast Arm
730F002	1	Each	Metal Traffic Signal Pole With 70 Ft Mast Arm
730G001	8	Each	Metal Traffic Signal Strain Pole
730K000	11	Each	Traffic Signal Junction Box
730L002	72	LF	1", Metallic, Conduit
730L003	398	LF	1", Non-Metallic, Conduit
730L005	299	LF	2", Non-Metallic, Conduit
730N000	11	Each	Luminaire Extension Assembly,
730P022	41	Each	Vehicular Signal Head, 12 Inch, 3 Section, Type LED
730P023	19	Each	Vehicular Signal Head, 12 Inch, 4 Section, Type LED
730Q011	26	Each	Pedestrian Signal Head, Type LED
730R022	3	Each	Controller Assembly, Type III, 8 Phase
730U400	1	LS	Radar Detection System (SR-8 at Landline Road)
730U401	1	LS	Radar Detection System (SR-8 at Medical Center Parkway)
730U402	1	LS	Radar Detection System (SR-8 at Bell Road)

Item No.	Quantity	Units	Description
730U403	1	LS	Radar Detection System (SR-8 at Summerfield Road)
730U404	1	LS	Radar Detection System (SR-8 at Montague Street)
730U405	1	LS	Radar Detection System (SR-8 at Broad Street)
730U406	1	LS	Radar Detection System (SR-8 at Franklin Street)
730U407	1	LS	Radar Detection System (SR-8 at Marie Foster Street)
730U408	1	LS	Radar Detection System (SR-8 at Walmart Entrance)
730U409	1	LS	Radar Detection System (SR-8 at US-80)
740B000	360	SQFT	Construction Signs
740D000	20	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740I002	40	Each	Warning Lights, Type B
740M001	100	Each	Ballast For Cone
742A001	2	Each	Portable Changeable Message Sign, Type 2
756A028	390	LF	6" Electrical Conduit, 1 Line, Type 5 Installation