

**Alabama Department of Transportation
Proposal Item Summary**

046. IM-I085(361)

LEE COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on I-85 from 1.340 miles south of the Andrews Road Interchange (Exit 66) in Opelika to the Chambers County Line. Length 3.774 mi.

The Bracket Estimate on this project is from \$1,223,091 to \$1,494,889.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
408B000	120,250	SQYD	Micro-Milling Existing Pavement(Approximately 0.00" Thru 1.00" Thick)
410H000	1	Each	Material Remixing Device
420A015	5,680	Ton	Polymer Modified Open Graded Friction Course
420B000	22,700	Gal	Open Graded Friction Course Tack Coat
424B283	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424B287	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range E
432A000	26,350	SQYD	High Density Mineral Bond
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 75,000.00)
701A227	8	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	8	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	8	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	2,950	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	16	Mile	Broken Temporary Traffic Stripe
701C001	32	Mile	Solid Temporary Traffic Stripe
701G142	408	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	408	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	408	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	816	LF	Solid Traffic Stripe Removed (Plastic)
701H006	408	LF	Broken Traffic Stripe Removed (Plastic)
703A002	2,900	SQFT	Traffic Control Markings, Class 2, Type A
703D001	1,800	SQFT	Temporary Traffic Control Markings
705A030	520	Each	Pavement Markers, Class A-H, Type 2-C
705A031	555	Each	Pavement Markers, Class A-H, Type 1-A
730H001	800	LF	Loop Wire
731A010	1	Each	Traffic Counting Units, Type K
740B000	2,246	SQFT	Construction Signs
740C000	36	SQFT	Special Construction Signs
740D000	500	Each	Channelizing Drums
740E000	500	Each	Cones (36 Inches High)
740M001	500	Each	Ballast For Cone
741C010	4	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	8	Each	Portable Changeable Message Sign, Type 2