

**Alabama Department of Transportation
Proposal Item Summary**

052. NH-0012(566)

HOUSTON COUNTY

Contract Time: 75 Working Days

DBE Goal Percent: 8.00

for constructing the Planing, Resurfacing, Guardrail Replacement, and Traffic Stripe on SR-12 (US-84) from west of the intersection of South Broad Street in Cowarts to west of the junction of Thompson Road northwest of Pansey. Length 7.139 mi.

The Bracket Estimate on this project is from \$3,855,534 to \$4,712,320.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	1,600	LF	Removing Guardrail
206E008	8	Each	Removing Guardrail End Anchor (All Type)
209A000	13	Each	Mailbox Reset, Single
209A001	1	Each	Mailbox Reset, Double
209A002	6	Each	Mailbox Reset, Multiple
210A000	4,000	CUYD	Unclassified Excavation
212A000	1,047	STA	Machine Grading Shoulders
405A000	35,769	Gal	Tack Coat
407B000	28	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	364,469	SQYD	Micro-Milling Existing Pavement(Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A281	19,277	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range E
424A361	9,797	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	995	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B285	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range E
424B702	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range E
428A001	27	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
630A001	1,885	LF	Steel Beam Guardrail, Class A, Type 2
630C001	2	Each	Guardrail End Anchor, Type 8
630C080	6	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	2,500	CUYD	Topsoil
652A100	28	Acre	Seeding
652C000	140	Acre	Mowing
654A001	6,974	SQYD	Solid Sodding (Bermuda)
656A010	28	Acre	Mulching
665A000	10	Acre	Temporary Seeding
665B001	30	Ton	Temporary Mulching
665E000	3,000	SQYD	Polyethylene
665G000	100	Each	Sand Bags
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
665P005	5	Each	Inlet Protection, Stage 3 Or 4
665Q002	500	LF	Wattle

Item No.	Quantity	Units	Description
666A001	28	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 218,000.00)
701A227	16	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	18	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	15	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	19,716	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	58	Mile	Broken Temporary Traffic Stripe
701C001	67	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
703A002	9,022	SQFT	Traffic Control Markings, Class 2, Type A
703B002	2,877	SQFT	Traffic Control Legends, Class 2, Type A
703D001	20,185	SQFT	Temporary Traffic Control Markings
703E001	2,184	SQFT	Temporary Traffic Control Legends
705A030	2,267	Each	Pavement Markers, Class A-H, Type 2-C
705A037	141	Each	Pavement Markers, Class A-H, Type 2-D
728A000	1	Each	Truck Mounted Impact Attenuator Unit
740B000	1,876	SQFT	Construction Signs
740D000	125	Each	Channelizing Drums
740E000	150	Each	Cones (36 Inches High)
740I002	10	Each	Warning Lights, Type B
740M001	150	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2