

**Alabama Department of Transportation
Proposal Item Summary**

055. NH-0021(565)

MONTGOMERY COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-21 (West South Boulevard) from the junction of SR-3 (US-31) to the I-65 Interchange (Site1) and on SR-3 (US-31/West Boulevard) from the junction of SR-21 to the junction of Estate Avenue (Site 2). Length 1.248 mi.

The Bracket Estimate on this project is from \$1,224,811 to \$1,496,991.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
212A000	125	STA	Machine Grading Shoulders
305B077	500	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
401A004	30,200	SQYD	Bituminous Treatment E
401A006	33,130	SQYD	Bituminous Treatment G
405A000	2,785	Gal	Tack Coat
407B000	6	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	35,290	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
408A054	33,130	SQYD	Planing Existing Pavement (Approximately 3.10" Thru 4.0" Thick)
410H000	1	Each	Material Remixing Device
410I000	1	Each	Smoothness Testing, Certified Inertial Profiler
424A276	3,660	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range E
424A359	280	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B280	4,350	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range E
424B653	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	3	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
650A000	300	CUYD	Topsoil
665G000	100	Each	Sand Bags
665J002	250	LF	Silt Fence
665O001	250	LF	Silt Fence Removal
665Q002	250	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 63,100.00)
701A227	3	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	4	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,335	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	7	Mile	Broken Temporary Traffic Stripe
701C001	22	Mile	Solid Temporary Traffic Stripe
701G142	390	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	390	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	780	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	1,170	LF	Solid Traffic Stripe Removed (Plastic)

Item No.	Quantity	Units	Description
701H006	390	LF	Broken Traffic Stripe Removed (Plastic)
703A002	8,000	SQFT	Traffic Control Markings, Class 2, Type A
703B002	718	SQFT	Traffic Control Legends, Class 2, Type A
703D001	4,200	SQFT	Temporary Traffic Control Markings
705A030	15	Each	Pavement Markers, Class A-H, Type 2-C
705A031	210	Each	Pavement Markers, Class A-H, Type 1-A
705A032	1,080	Each	Pavement Markers, Class A-H, Type 1-B
705A037	100	Each	Pavement Markers, Class A-H, Type 2-D
705A038	540	Each	Pavement Markers, Class A-H, Type 2-E
740B000	773	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	500	Each	Cones (36 Inches High)
740M001	500	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit