

**Alabama Department of Transportation  
Proposal Item Summary**

**056. NH-0113(502)**

**ESCAMBIA COUNTY**

Contract Time: 150 Working Days

DBE Goal Percent: 5.00

for constructing the Planing, Resurfacing, Bridge Rail Retrofit, and Traffic Stripe on SR-113 from the junction of SR-3 (US-31) in Flomaton to the I-65 Interchange. Length 13.683 mi.

The Bracket Estimate on this project is from \$5,206,181 to \$6,363,110.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

*The Principal Items of work are approximately as follows:*

| Item No. | Quantity | Units | Description  |
|----------|----------|-------|--|
| 212A000  | 722      | STA   | Machine Grading Shoulders  |
| 405A000  | 53,847   | Gal   | Tack Coat  |
| 407B000  | 32       | Mile  | Joint Sealant For Hot Mix Asphalt Pavement   |
| 408A052  | 538,232  | SQYD  | Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)  |
| 408A054  | 284      | SQYD  | Planing Existing Pavement (Approximately 3.10" Thru 4.0" Thick)  |
| 410H000  | 1        | Each  | Material Remixing Device   |
| 424A360  | 52,424   | Ton   | Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D           |
| 424A369  | 1,400    | Ton   | Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D |
| 424B650  | 47       | Ton   | Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D              |
| 424B655  | 50       | Ton   | Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D      |
| 424B659  | 350      | Ton   | Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1" Maximum Aggregate Size Mix, ESAL Range C/D      |
| 428A001  | 51       | Mile  | Scoring Bituminous Pavement Surface  |
| 600A000  | 1        | LS    | Mobilization   |
| 629E015  | 689      | LF    | Bridge Rail Retrofit, Type SC(CB)  |
| 650A000  | 750      | CUYD  | Topsoil  |
| 652A100  | 40       | Acre  | Seeding  |
| 652C000  | 220      | Acre  | Mowing   |
| 656A010  | 40       | Acre  | Mulching   |
| 665J002  | 2,500    | LF    | Silt Fence   |
| 665O001  | 2,500    | LF    | Silt Fence Removal   |
| 665Q002  | 1,500    | LF    | Wattle   |
| 698A000  | 1        | LS    | Construction Fuel (Maximum Bid Limited to \$ 120,000.00)   |
| 701A227  | 29       | Mile  | Solid White, Class 2, Type A Traffic Stripe (5" Wide)  |
| 701A230  | 28       | Mile  | Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)   |
| 701A239  | 27       | Mile  | Broken White, Class 2, Type A Traffic Stripe (5" Wide)   |
| 701A244  | 2        | Mile  | Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)  |
| 701B207  | 14,158   | LF    | Dotted, Class 2, Type A Traffic Stripe (5" Wide)   |
| 701C000  | 54       | Mile  | Broken Temporary Traffic Stripe  |
| 701C001  | 57       | Mile  | Solid Temporary Traffic Stripe   |
| 701G142  | 506      | LF    | Broken White, Class W, Type A Traffic Stripe (5" Wide)   |
| 701G146  | 1,201    | LF    | Solid White, Class W, Type A Traffic Stripe (5"Wide)   |
| 701G154  | 1,201    | LF    | Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)   |
| 701G251  | 600      | LF    | Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)   |
| 701H001  | 2,202    | LF    | Solid Traffic Stripe Removed (Plastic)   |
| 701H006  | 406      | LF    | Broken Traffic Stripe Removed (Plastic)  |

| <b>Item No.</b> | <b>Quantity</b> | <b>Units</b> | <b>Description</b>                              |
|-----------------|-----------------|--------------|---|
| 703A002         | 5,519           | SQFT         | Traffic Control Markings, Class 2, Type A       |
| 703B002         | 2,150           | SQFT         | Traffic Control Legends, Class 2, Type A        |
| 703D001         | 3,256           | SQFT         | Temporary Traffic Control Markings              |
| 705A030         | 2,590           | Each         | Pavement Markers, Class A-H, Type 2-C           |
| 705A032         | 282             | Each         | Pavement Markers, Class A-H, Type 1-B           |
| 705A037         | 221             | Each         | Pavement Markers, Class A-H, Type 2-D           |
| 705A038         | 161             | Each         | Pavement Markers, Class A-H, Type 2-E           |
| 730H001         | 3,400           | LF           | Loop Wire                                       |
| 730L005         | 150             | LF           | 2", Non-Metallic, Conduit                       |
| 740B000         | 1,397           | SQFT         | Construction Signs                              |
| 740D000         | 25              | Each         | Channelizing Drums                              |
| 740E000         | 250             | Each         | Cones (36 Inches High)                          |
| 740M001         | 250             | Each         | Ballast For Cone                                |
| 741C010         | 1               | Each         | Portable Sequential Arrow And Chevron Sign Unit |