

**Alabama Department of Transportation
Proposal Item Summary**

060. STPAA-0017(575)

LAUDERDALE COUNTY

Contract Time: 40 Working Days

DBE Goal Percent: 7.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-17 from the junction of SR-133 in Florence to 0.170 mile north of the junction of CR-172. Length 5.570 mi.

The Bracket Estimate on this project is from \$1,117,681 to \$1,366,054.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	10,707	Gal	Tack Coat
407B000	8	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	107,064	SQYD	Micro-Milling Existing Pavement(Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	8,298	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
430B042	706	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type A)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 62,900.00)
701A227	10	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	10	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	3	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	748	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	9	Mile	Broken Temporary Traffic Stripe
701C001	37	Mile	Solid Temporary Traffic Stripe
703A002	2,118	SQFT	Traffic Control Markings, Class 2, Type A
703B002	448	SQFT	Traffic Control Legends, Class 2, Type A
703D001	3,132	SQFT	Temporary Traffic Control Markings
703E001	314	SQFT	Temporary Traffic Control Legends
705A032	175	Each	Pavement Markers, Class A-H, Type 1-B
705A037	450	Each	Pavement Markers, Class A-H, Type 2-D
705A038	20	Each	Pavement Markers, Class A-H, Type 2-E
730H001	3,810	LF	Loop Wire
730I001	1,320	LF	Loop Detector Lead-In-Cable
730K000	2	Each	Traffic Signal Junction Box
730L005	230	LF	2", Non-Metallic, Conduit
740B000	1,409	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	300	Each	Cones (36 Inches High)
740M001	300	Each	Ballast For Cone
740O000	1	Each	Pilot Car
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit