

**Alabama Department of Transportation
Proposal Item Summary**

065. STPAA-5117(252)

MONTGOMERY COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on CR-24 (Cloverfield/Federal Road) from the Lowndes County Line to the intersection of SR-3 (US-31). Length 2.955 mi.

The Bracket Estimate on this project is from \$525,346 to \$642,089.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	7,631	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	3,138	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A360	3,148	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	2,194	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
430B043	625	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 29,600.00)
701A231	6	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	8	Mile	Solid Temporary Traffic Stripe
703A002	125	SQFT	Traffic Control Markings, Class 2, Type A
705A032	86	Each	Pavement Markers, Class A-H, Type 1-B
705A037	293	Each	Pavement Markers, Class A-H, Type 2-D
730H001	324	LF	Loop Wire
740B000	347	SQFT	Construction Signs
740E000	25	Each	Cones (36 Inches High)
740M001	25	Each	Ballast For Cone
740O000	1	Each	Pilot Car