

**Alabama Department of Transportation
Proposal Item Summary**

068. STPAA-HSIP-0007(547)

ST. AND CLAIR COUNTIES

Contract Time: 45 Working Days

DBE Goal Percent: 3.00

for constructing the Safety Widening, Planing, Resurfacing, and Traffic Stripe on SR-7 (US-11) from the junction of SR-23 in Springville to north of the junction of Sweatt Road in Ashville. Length 9.938 mi.

The Bracket Estimate on this project is from \$2,535,143 to \$3,098,508.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	139	SQYD	Removing Concrete Driveway
209A000	8	Each	Mailbox Reset, Single
209A002	1	Each	Mailbox Reset, Multiple
305B077	3,674	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
327D021	4,634	Ton	Plant Mix Bituminous Base, Widening, Mix 2
401A004	164,279	SQYD	Bituminous Treatment E
405A000	17,116	Gal	Tack Coat
407B000	10	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	145,691	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A361	16,454	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	250	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B658	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	20	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
665A000	5	Acre	Temporary Seeding
665B001	15	Ton	Temporary Mulching
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
665Q002	1,000	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 149,000.00)
701A227	20	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	8	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	23	Mile	Broken Temporary Traffic Stripe
701C001	86	Mile	Solid Temporary Traffic Stripe
701G146	424	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	424	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	848	LF	Solid Traffic Stripe Removed (Tape)
703A002	488	SQFT	Traffic Control Markings, Class 2, Type A
703D001	976	SQFT	Temporary Traffic Control Markings
705A032	261	Each	Pavement Markers, Class A-H, Type 1-B
705A037	805	Each	Pavement Markers, Class A-H, Type 2-D
705A038	500	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,816	SQFT	Construction Signs

Item No.	Quantity	Units	Description
7400000	1 Each	Pilot Car	