

**Alabama Department of Transportation
Proposal Item Summary**

083. STPNU-6218(250)

TALLAPOOSA COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Resurfacing and Traffic Stripe on CR-45 (Lovely Road) from the junction of SR-49 to the junction of SR-50. Length 8.558 mi.

The Bracket Estimate on this project is from \$797,821 to \$975,115.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
401B108	99,392	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	700	Gal	Tack Coat
407B000	9	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A346	7,456	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	2,230	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 44,900.00)
701A004	18	Mile	Solid White, Class 1, Type A Traffic Stripe
701A008	3	Mile	Broken Yellow, Class 1, Type A Traffic Stripe
701A012	16	Mile	Solid Yellow, Class 1, Type A Traffic Stripe
701C000	3	Mile	Broken Temporary Traffic Stripe
701C001	28	Mile	Solid Temporary Traffic Stripe
703A000	280	SQFT	Traffic Control Markings, Class 1, Type A
705A032	92	Each	Pavement Markers, Class A-H, Type 1-B
705A037	835	Each	Pavement Markers, Class A-H, Type 2-D
740B000	249	SQFT	Construction Signs
740O000	1	Each	Pilot Car