

**Alabama Department of Transportation
Proposal Item Summary**

089. STPOA-8121(601)

ETOWAH COUNTY

Contract Time: 125 Working Days

DBE Goal Percent: 10.00

for constructing the Widening, Planing, Resurfacing, and Traffic Stripe on South 11th Street from the junction of CR-205 (Black Creek Parkway) to the junction of Piedmont Avenue in Gadsden. Length 0.626 mi.

The Bracket Estimate on this project is from \$1,775,620 to \$2,170,202.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$27.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 2 Acres)
206C000	875	SQYD	Removing Concrete Sidewalk
206C002	412	SQYD	Removing Concrete Slope Paving
206C010	297	SQYD	Removing Concrete Driveway
206D000	263	LF	Removing Pipe
206D002	405	LF	Removing Curb
206D003	3,932	LF	Removing Curb And Gutter
206D005	801	LF	Removing Gutter
206E001	4	Each	Removing Inlets
206E003	1	Each	Removing Manholes
210A000	5,591	CUYD	Unclassified Excavation
210D011	581	CUYD	Borrow Excavation (A4 Or Better)
214A000	532	CUYD	Structure Excavation
214B001	168	CUYD	Foundation Backfill, Commercial
305B071	100	Ton	Coarse Aggregate, Section 801, For Miscellaneous Use
305B078	1,162	Ton	Crushed Aggregate, Section 825, Type B, For Miscellaneous Use
401A000	3,683	SQYD	Bituminous Treatment A
405A000	1,047	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	11,392	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A340	1,048	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B635	265	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	158	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B643	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B666	447	Ton	Superpave Bituminous Concrete Lower Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424C340	657	Ton	Superpave Bituminous Concrete Base Layer, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B028	25	Ton	Aggregate Surfacing (ALDOT #57, #78 Or #467)
517D002	178	LF	Galvanized Steel Sidewalk Handrail
529A020	186	SQFT	Retaining Wall # 1
530A001	154	LF	18" Roadway Pipe (Class 3 R.C.)
530A003	41	LF	30" Roadway Pipe (Class 3 R.C.)
533A098	286	LF	18" Storm Sewer Pipe (Class 3 R.C.)
533A101	8	LF	36" Storm Sewer Pipe (Class 3 R.C.)
600A000	1	LS	Mobilization

Item No.	Quantity	Units	Description
610C001	10	Ton	Loose Riprap, Class 2
610D003	153	SQYD	Filter Blanket, Geotextile
614A000	412	CUYD	Slope Paving
618A000	344	SQYD	Concrete Sidewalk, 4" Thick
618A001	2,134	SQYD	Concrete Sidewalk, 6" Thick
618B003	139	SQYD	Concrete Driveway, 6" Thick (Includes Wire Mesh)
619A002	1	Each	18" Roadway Pipe End Treatment, Class 1
620A000	20	CUYD	Minor Structure Concrete
621A005	2	Each	Junction Boxes, Type 1
621C015	4	Each	Inlets, Type S1 Or S3 (1 Wing)
621C017	3	Each	Inlets, Type S1 Or S3 (2 Wing)
621C018	1	Each	Inlets, Type S2 Or S4 (2 Wing)
621C088	1	Each	Inlets, Type S2 Or S4 (2 Wing) (Modified)
621C100	1	Each	Inlets, Type PR
621C110	1	Each	Inlets, Type PD-6
621D015	1	Each	Inlet Units, Type S1 Or S3
623A001	987	LF	Concrete Gutter (Valley)
623B000	297	LF	Concrete Curb, Type N
623B001	220	LF	Concrete Curb, Type N Special
623C000	3,929	LF	Combination Curb & Gutter, Type C
637A000	599	LF	Fence Reset
650A000	523	CUYD	Topsoil
652A100	1	Acre	Seeding
654A001	6,286	SQYD	Solid Sodding (Bermuda)
656A010	1	Acre	Mulching
665A000	2	Acre	Temporary Seeding
665B001	12	Ton	Temporary Mulching
665E000	500	SQYD	Polyethylene
665F000	500	Each	Hay Bales
665G000	150	Each	Sand Bags
665I000	5	Ton	Temporary Riprap, Class 2
665J002	2,315	LF	Silt Fence
665N000	175	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665O001	2,315	LF	Silt Fence Removal
665P005	13	Each	Inlet Protection, Stage 3 Or 4
665Q002	250	LF	Wattle
666A001	2	Acre	Pest Control Treatment
674A000	300	LF	Construction Safety Fence
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 126,500.00)
701A227	2	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	2	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	384	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	1	Mile	Broken Temporary Traffic Stripe
701C001	2	Mile	Solid Temporary Traffic Stripe
701G154	50	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A002	5,612	SQFT	Traffic Control Markings, Class 2, Type A
703A011	150	SQFT	Traffic Control Markings, Class W, Type A
703B002	421	SQFT	Traffic Control Legends, Class 2, Type A
703D001	3,434	SQFT	Temporary Traffic Control Markings
703E001	229	SQFT	Temporary Traffic Control Legends
705A030	24	Each	Pavement Markers, Class A-H, Type 2-C
705A032	121	Each	Pavement Markers, Class A-H, Type 1-B
705A037	90	Each	Pavement Markers, Class A-H, Type 2-D

Item No.	Quantity	Units	Description
705A038	61	Each	Pavement Markers, Class A-H, Type 2-E
710A115	132	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick Or Steel Flat Sign Panels 14 Gauge (Type III Or Type IV Background)
710A126	91	SQFT	Class 8, Aluminum Flat Sign Panels 0.08" Thick Or Steel Flat Sign Panels 14 Gauge (Type IX Background)
710B021	377	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
730A000	1	LS	Removal Of Existing Traffic Control Unit (South 11th Street at Black Parkway)
730C000	1	LS	Furnishing And Installing Traffic Control Unit (South 11th Street at Black Parkway)
730E000	4	Each	Metal Traffic Signal Pole Foundation
730G001	4	Each	Metal Traffic Signal Strain Pole
730H001	1,430	LF	Loop Wire
730I001	650	LF	Loop Detector Lead-In-Cable
730J010	4	Each	Vehicle Loop Detector
730K000	1	Each	Traffic Signal Junction Box
730L003	50	LF	1", Non-Metallic, Conduit
730L004	25	LF	2", Metallic, Conduit
730L005	100	LF	2", Non-Metallic, Conduit
730N000	3	Each	Luminaire Extension Assembly, 12 Feet
730P022	6	Each	Vehicular Signal Head, 12 Inch, 3 Section, Type LED
730P023	1	Each	Vehicular Signal Head, 12 Inch, 4 Section, Type LED
730Q011	4	Each	Pedestrian Signal Head, Type LED
730R022	1	Each	Controller Assembly, Type III, 8 Phase
740B000	673	SQFT	Construction Signs
740D000	65	Each	Channelizing Drums
740E000	25	Each	Cones (36 Inches High)
740F002	19	Each	Barricades, Type III
740I005	10	Each	Warning Lights, Type B (Detachable Head)
740M001	25	Each	Ballast For Cone
740O000	1	Each	Pilot Car
742A001	2	Each	Portable Changeable Message Sign, Type 2