

**Alabama Department of Transportation
Proposal Item Summary**

092. 99-509-490-188-602 & 99-509-491-188-700

MOBILE COUNTY

Contract Time: 150 Working Days

for constructing the Seawall Replacement on SR-188 located at MP 10.220 to include the Relocation of Movable Barriers and Gate Arms at the J. A. Wintzell Memorial Bridge in Bayou La Batre.

The Bracket Estimate on this project is from \$1,949,859 to \$2,383,161.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$41.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D008	106	LF	Removing Retaining Wall
206D011	324	LF	Removing Fence
210A000	29	CUYD	Unclassified Excavation
210D009	141	CUYD	Borrow Excavation (A-3)
502A000	1,329	LB	Steel Reinforcement
505E000	3,107	LF	Permanent Steel Sheet Piling
508B000	1	Each	Structural Steel Superstructure,
510B001	18	CUYD	Bridge Concrete, Class A
517A002	114	LF	Galvanized Steel Pipe Handrail
520A100	1	LS	Repairs to Existing Bridge, Replacement of Traffic Gates
520A101	1	LS	Repairs to Existing Bridge, Replacement of Traffic Barriers
520A102	1	LS	Repairs to Existing Bridge, Replacement of Span Locks
600A000	1	LS	Mobilization
610A004	85	SQYD	Loose Riprap, Class 2, 24" Thick
610D003	85	SQYD	Filter Blanket, Geotextile
618A000	48	SQYD	Concrete Sidewalk, 4" Thick
620A000	5	CUYD	Minor Structure Concrete
634A010	15	LF	Industrial Fence, 6 Feet High (With Top Rail)
634D008	5	Each	Gate, 4 Feet Wide, Complete With Fittings (Without Barbed Wire)
634D036	1	Each	Gate, 6 Feet Wide, Complete With Fittings (Without Barbed Wire)
634E000	157	LF	Industrial Fence, 6 Feet High, Special Mounting
634E005	165	LF	Industrial Fence, 4 Feet High, Special Mounting
635B000	1	Each	Gate, 4 Feet Wide
665E000	200	SQYD	Polyethylene
665J002	100	LF	Silt Fence
665L000	220	LF	Floating Basin Boom
665O001	100	LF	Silt Fence Removal
674A000	200	LF	Construction Safety Fence
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 60,000.00)
740B000	717	SQFT	Construction Signs
740D000	115	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740F002	2	Each	Barricades, Type III
740I005	28	Each	Warning Lights, Type B (Detachable Head)
740M001	50	Each	Ballast For Cone
742A001	4	Each	Portable Changeable Message Sign, Type 2