

Alabama Department of Transportation
Proposal Item Summary

006. ACBR60389-ATRP(011)

CLEBURNE COUNTY

Contract Time: 90 Working Days

DBE Goal Percent: 1.00

for constructing the Bridge Replacement and Approaches on CR-49 over Baily Branch. Length 0.065 mi.

The Bracket Estimate on this project is from \$414,315 to \$506,385.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1 LS		Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
206A000	1 LS		Removal Of Old Bridge, Station 15+00.00
206D001	165 LF		Removing Guardrail
206E008	4 Each		Removing Guardrail End Anchor (All Type)
210A000	203 CUYD		Unclassified Excavation
210D001	300 CUYD		Borrow Excavation (Loose Truckbed Measurement)
214A000	818 CUYD		Structure Excavation
214B001	149 CUYD		Foundation Backfill, Commercial
230A000	4 RBST		Roadbed Processing
301A012	733 SQYD		Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	733 SQYD		Bituminous Treatment A
405A000	18 Gal		Tack Coat
408A053	120 SQYD		Planing Existing Pavement (Approximately 2.10" Thru 3.0" Thick)
424A340	71 Ton		Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B636	106 Ton		Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	16 Ton		Aggregate Surfacing (1" Down, Crusher Run)
502A000	31,605 LB		Steel Reinforcement
524A010	227 CUYD		Culvert Concrete
530A253	10 LF		24" Roadway Pipe (14 Gauge C.C.M.P.I.) (Extension)
600A000	1 LS		Mobilization
610C001	315 Ton		Loose Riprap, Class 2
610D003	215 SQYD		Filter Blanket, Geotextile
630A001	256 LF		Steel Beam Guardrail, Class A, Type 2
630C080	4 Each		Guardrail End Anchor, Type 20 Series (MASH)
650A000	129 CUYD		Topsoil
652A100	1 Acre		Seeding
656A010	1 Acre		Mulching
659C001	1,263 SQYD		Erosion Control Product, Type S3
665A000	1 Acre		Temporary Seeding
665B001	3 Ton		Temporary Mulching
665F000	100 Each		Hay Bales
665J002	445 LF		Silt Fence
665N000	50 Ton		Temporary Coarse Aggregate,ALDOT Number 1
665O001	445 LF		Silt Fence Removal
665Q002	150 LF		Wattle
666A001	1 Acre		Pest Control Treatment
680A001	1 LS		Geometric Controls
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 17,000.00)
701G249	700 LF		Solid White, Class 2, Type A Traffic Stripe

Item No.	Quantity	Units	Description
701G263	700	LF	Solid Yellow, Class 2, Type A Traffic Stripe
705A037	14	Each	Pavement Markers, Class A-H, Type 2-D
740B000	199	SQFT	Construction Signs
740F002	8	Each	Barricades, Type III
740I002	4	Each	Warning Lights, Type B