

Alabama Department of Transportation
Proposal Item Summary

008. ACBRZ60336-ATRP(006) & ACBRZ60344-ATRP(011)

HALE COUNTY

Contract Time: 130 Working Days

DBE Goal Percent: 2.00

for constructing the Bridge Replacements and Approaches on CR-192 (Duncan Loop Road) over Hardin Creek east of Stewart (Site 1) and on CR-198 (David Campbell Road) over Gile Creek northeast of Havana (Site 2). Length 0.197 mi.

The Bracket Estimate on this project is from \$776,011 to \$948,457.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$14.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
206A000	1	LS	Removal Of Old Bridge, Station 11+76.90
206A001	1	LS	Removal Of Old Bridge, Station 14+96.98
210A000	1,194	CUYD	Unclassified Excavation
210D021	2,860	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
214A000	1,316	CUYD	Structure Excavation
214B001	320	CUYD	Foundation Backfill, Commercial
230A000	11	RBST	Roadbed Processing
301A012	2,342	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	2,342	SQYD	Bituminous Treatment A
405A000	167	Gal	Tack Coat
424A340	174	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B636	312	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	52	Ton	Aggregate Surfacing (1" Down, Crusher Run)
502A000	53,253	LB	Steel Reinforcement
524A011	447	CUYD	Culvert Concrete (Cast In Place)
600A000	1	LS	Mobilization
602A000	36	Each	Right Of Way Markers
610C001	639	Ton	Loose Riprap, Class 2
610D003	760	SQYD	Filter Blanket, Geotextile
637A001	660	LF	Fence Reset (Includes All Types)
650A000	548	CUYD	Topsoil
652A100	2	Acre	Seeding
656A010	2	Acre	Mulching
665A000	2	Acre	Temporary Seeding
665B001	6	Ton	Temporary Mulching
665I000	250	Ton	Temporary Riprap, Class 2
665J002	2,690	LF	Silt Fence
665O001	2,690	LF	Silt Fence Removal
665Q002	180	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 39,000.00)
740B000	274	SQFT	Construction Signs
740F002	12	Each	Barricades, Type III
740I002	6	Each	Warning Lights, Type B