

Alabama Department of Transportation
Proposal Item Summary

022. FLAP-STPNU-FLAP(026)

CLARKE COUNTY

Contract Time: 30 Working Days

for constructing the Resurfacing and Traffic Stripe on CR-39 from the junction of Silver Creek Access Road to a point 1.050 miles south. Length 1.050 mi.

The Bracket Estimate on this project is from \$176,584 to \$215,825.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
212A000	112 STA		Machine Grading Shoulders
405A000	1,400 Gal		Tack Coat
407B000	2 Mile		Joint Sealant For Hot Mix Asphalt Pavement
424A340	1,151 Ton		Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	100 Ton		Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	300 Ton		Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1 LS		Mobilization
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 9,500.00)
701A077	3 Mile		Solid Yellow, Class 2T, Type A Traffic Stripe (5" Wide)
701C001	3 Mile		Solid Temporary Traffic Stripe
703A004	20 SQFT		Traffic Control Markings, Class 2T, Type A
705A037	145 Each		Pavement Markers, Class A-H, Type 2-D
740B000	168 SQFT		Construction Signs
740O000	1 Each		Pilot Car