

Alabama Department of Transportation
Proposal Item Summary

035. IM-1165(303)

MOBILE COUNTY

Contract Time: 60 Working Days

DBE Goal Percent: 5.00

for constructing the Planing, Resurfacing, Sidewalk Installation, and Traffic Stripe on I-165 (Service Roads) from 0.040 mile south of the junction of Bay Bridge Road to 0.080 mile north of the intersection of Whistler Street in Mobile. Length 1.630 mi.

The Bracket Estimate on this project is from \$1,603,050 to \$1,959,283.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$23.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	316	SQYD	Removing Concrete Sidewalk
206C002	127	SQYD	Removing Concrete Slope Paving
206D000	120	LF	Removing Pipe
206D003	539	LF	Removing Curb And Gutter
212A000	287	STA	Machine Grading Shoulders
405A000	12,071	Gal	Tack Coat
407B000	18	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	120,710	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	11,167	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A366	25	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	25	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
430B040	25	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type B)
532A032	120	LF	18" Slotted Drain Pipe
534E001	1,660	LF	Cleaning Existing Pipe (Less Than Or Equal To 48" Horizontal Opening)
600A000	1	LS	Mobilization
618A000	356	SQYD	Concrete Sidewalk, 4" Thick
623C000	539	LF	Combination Curb & Gutter, Type C
650A000	50	CUYD	Topsoil
652C000	186	Acre	Mowing
654A001	197	SQYD	Solid Sodding (Bermuda)
665E000	500	SQYD	Polyethylene
665G000	50	Each	Sand Bags
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
665Q002	200	LF	Wattle
666A001	1	Acre	Pest Control Treatment
674A000	3,120	LF	Construction Safety Fence
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 85,600.00)
701A227	5	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	3	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	4	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B063	10,919	LF	Dotted, Class 2, Type A Traffic Stripe(Lane Drop 10" Wide)
701B207	2,326	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	12	Mile	Broken Temporary Traffic Stripe

Item No.	Quantity	Units	Description
701C001	16	Mile	Solid Temporary Traffic Stripe
703A002	12,609	SQFT	Traffic Control Markings, Class 2, Type A
703B002	1,166	SQFT	Traffic Control Legends, Class 2, Type A
703B011	394	SQFT	Traffic Control Legends, Class W, Type A
703D001	11,706	SQFT	Temporary Traffic Control Markings
705A030	1,863	Each	Pavement Markers, Class A-H, Type 2-C
705A031	770	Each	Pavement Markers, Class A-H, Type 1-A
730A012	1	LS	Removal Of Existing Traffic Control Unit (Partial) (I-165 Service Road at Bay Bridge Road)
730A013	1	LS	Removal Of Existing Traffic Control Unit (Partial) (I-165 Service Road at Martin Luther King)
730A014	1	LS	Removal Of Existing Traffic Control Unit (Partial) (I-165 Service Road at Wilson Avenue)
730A015	1	LS	Removal Of Existing Traffic Control Unit (Partial) (I-165 Service Road at Price Avenue)
730A016	1	LS	Removal Of Existing Traffic Control Unit (Partial) (I-165 Service Road at Whistler Street)
730C000	1	LS	Furnishing And Installing Traffic Control Unit (I-165 Service Road at Bay Bridge Road)
730C001	1	LS	Furnishing And Installing Traffic Control Unit (I-165 Service Road at Martin Luther King)
730C002	1	LS	Furnishing And Installing Traffic Control Unit (I-165 Service Road at Wilson Avenue)
730C003	1	LS	Furnishing And Installing Traffic Control Unit (I-165 Service Road at Price Avenue)
730C004	1	LS	Furnishing And Installing Traffic Control Unit (I-165 Service Road at Whistler Street)
730H001	16,275	LF	Loop Wire
730L005	1,120	LF	2", Non-Metallic, Conduit
730Q011	48	Each	Pedestrian Signal Head, Type LED
740B000	1,848	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	250	Each	Cones (36 Inches High)
740M001	250	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit