

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**039. NH-0009(568)**

**CRENSHAW COUNTY**

Contract Time: 85 Working Days

DBE Goal Percent: 4.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-9 (US-331) from the junction of SR-15 (US-29) in Luverne to north of the junction of CR-66 south of Highland Home. Length 17.010 mi.

The Bracket Estimate on this project is from \$3,645,697 to \$4,455,852.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
209A000	5	Each	Mailbox Reset, Single
209A001	2	Each	Mailbox Reset, Double
209A002	11	Each	Mailbox Reset, Multiple
212A000	1,569	STA	Machine Grading Shoulders
405A000	37,427	Gal	Tack Coat
407B000	22	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	374,270	SQYD	Micro-Milling Existing Pavement(Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A361	29,164	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	1,515	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
428A001	35	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
652A100	19	Acre	Seeding
652C000	116	Acre	Mowing
656A010	19	Acre	Mulching
665A000	7	Acre	Temporary Seeding
665B001	55	Ton	Temporary Mulching
665J002	150	LF	Silt Fence
665O001	150	LF	Silt Fence Removal
665Q002	150	LF	Wattle
666A001	19	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 195,000.00)
701A227	35	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	24	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	2	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	10	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	2,552	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	11	Mile	Broken Temporary Traffic Stripe
701C001	59	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G146	1,519	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)

Item No.	Quantity	Units	Description
701G154	1,519	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A002	20,924	SQFT	Traffic Control Markings, Class 2, Type A
703B002	762	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,215	SQFT	Temporary Traffic Control Markings
705A030	1,100	Each	Pavement Markers, Class A-H, Type 2-C
705A032	1,779	Each	Pavement Markers, Class A-H, Type 1-B
705A037	1,291	Each	Pavement Markers, Class A-H, Type 2-D
705A038	854	Each	Pavement Markers, Class A-H, Type 2-E
740B000	2,639	SQFT	Construction Signs
740C000	9	SQFT	Special Construction Signs
740D000	150	Each	Channelizing Drums
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit