

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**040. NH-0053(583)**

**LIMESTONE COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 5.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-53 from the junction of SR-251 in Ardmore to west of the I-65 Interchange. Length 2.523 mi.

The Bracket Estimate on this project is from \$766,748 to \$937,137.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206E008	9	Each	Removing Guardrail End Anchor (All Type)
405A000	4,115	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	41,148	SQYD	Micro-Milling Existing Pavement(Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A356	2,264	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B650	3,814	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
430B042	796	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type A)
600A000	1	LS	Mobilization
630C080	9	Each	Guardrail End Anchor, Type 20 Series (MASH)
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 48,000.00)
701A227	6	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	2	Mile	Broken Temporary Traffic Stripe
701C001	18	Mile	Solid Temporary Traffic Stripe
701G146	648	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	648	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	1,296	LF	Solid Traffic Stripe Removed (Plastic)
703A002	796	SQFT	Traffic Control Markings, Class 2, Type A
703D001	1,592	SQFT	Temporary Traffic Control Markings
705A032	35	Each	Pavement Markers, Class A-H, Type 1-B
705A037	225	Each	Pavement Markers, Class A-H, Type 2-D
730H001	1,135	LF	Loop Wire
730I001	585	LF	Loop Detector Lead-In-Cable
730K000	1	Each	Traffic Signal Junction Box
730L005	65	LF	2", Non-Metallic, Conduit
731A000	1	Each	Traffic Counting Units, Type A
731B000	1	Each	Pole for Mounting Traffic Detection Equipment
740B000	640	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
740O000	1	Each	Pilot Car