

Alabama Department of Transportation
Proposal Item Summary

003. ACBRZ60456-ATRP(008)

MARION COUNTY

Contract Time: 60 Working Days

DBE Goal Percent: 3.00

for constructing the Bridge Replacement on CR-9 over Barnesville Creek west of Hamilton. Length 0.022 mi.

The Bracket Estimate on this project is from \$499,739 to \$610,792.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1 LS		Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
206A000	1 LS		Removal Of Old Bridge, Station 10+09.00
210A000	450 CUYD		Unclassified Excavation
210D021	250 CUYD		Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
430B003	22 Ton		Aggregate Surfacing (ALDOT #57)
502A000	284 LB		Steel Reinforcement
505G003	24 Each		Pile Points (Type A, 12")
505G004	10 Each		Pile Points (Type A, 14")
505M002	1,076 LF		Steel Piling Furnished And Driven (HP 12x53)
505M012	645 LF		Steel Piling Furnished And Driven (HP 14 x 89)
507A000	2 Each		Wire Rope Abutment Anchor Assembly
510A007	24 CUYD		Bridge Substructure Concrete
511A000	40 Each		Elastomeric Bearing Type 1
512A008	2 Each		Precast Concrete Abutment Caps, 2'-0" Wide By 1'-7" Deep By 28'-0" Long
512B003	2 Each		Precast Concrete Intermediate Bent Caps, 2'-0" Wide By 1'-7" Deep By 27'-6" Long
512C017	15 Each		Precast Concrete Type 1 Span Section, 3'-6" By 2'-0" Deep By 39'-11 3/4" Long
512C025	6 Each		Precast Concrete Type 2C Span Section, 3'-6" By 2'-0" Deep By 39'-11 3/4" Long
512D025	2 Each		Precast Concrete Barrier Rail Intermediate Section, 39'-11" Long
512D030	4 Each		Precast Concrete Barrier Rail End Section, 39'-11 3/8" Long
512E001	16 Each		Precast Concrete Abutment Panels, Type A2
512F001	8 Each		Precast Concrete Wing Panels, Type W2
512G000	4 Each		Precast Concrete Abutment Wing Cap Panels
600A000	1 LS		Mobilization
610C001	480 Ton		Loose Riprap, Class 2
610D003	857 SQYD		Filter Blanket, Geotextile
630C003	4 Each		Guardrail End Anchor, Type 13
630C080	4 Each		Guardrail End Anchor, Type 20 Series (MASH)
665A000	1 Acre		Temporary Seeding
665B001	3 Ton		Temporary Mulching
665E000	200 SQYD		Polyethylene
665J002	2,040 LF		Silt Fence
665N000	45 Ton		Temporary Coarse Aggregate,ALDOT Number 1
680A001	1 LS		Geometric Controls
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 20,100.00)
740B000	231 SQFT		Construction Signs
740F002	8 Each		Barricades, Type III
740I002	4 Each		Warning Lights, Type B