

Alabama Department of Transportation
Proposal Item Summary

026. IM-1065(490)

CULLMAN AND MORGAN COUNTIES

Contract Time: 35 Working Days

DBE Goal Percent: 8.00

for constructing the Planing, Resurfacing, and Traffic Stripe on I-65 from Hurricane Creek (MP 315.665) to south of the CSX Railroad Bridge. Length 3.523 mi.

The Bracket Estimate on this project is from \$1,337,280 to \$1,634,453.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
408B000	109,717	SQYD	Micro-Milling Existing Pavement(Approximately 0.00" Thru 1.00" Thick)
410H000	1	Each	Material Remixing Device
420A015	4,938	Ton	Polymer Modified Open Graded Friction Course
420B000	21,944	Gal	Open Graded Friction Course Tack Coat
424B285	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range E
432A000	55,032	SQYD	High Density Mineral Bond
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 71,000.00)
701A227	7	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	7	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	7	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	2,971	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	14	Mile	Broken Temporary Traffic Stripe
701C001	28	Mile	Solid Temporary Traffic Stripe
701G142	1,937	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	1,937	LF	Solid White, Class W, Type A Traffic Stripe (5" Wide)
701G154	1,937	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	3,874	LF	Solid Traffic Stripe Removed (Plastic)
701H006	1,937	LF	Broken Traffic Stripe Removed (Plastic)
703A002	2,537	SQFT	Traffic Control Markings, Class 2, Type A
705A030	96	Each	Pavement Markers, Class A-H, Type 2-C
705A031	2,008	Each	Pavement Markers, Class A-H, Type 1-A
705A032	415	Each	Pavement Markers, Class A-H, Type 1-B
731A010	1	Each	Traffic Counting Units, Type K
740B000	2,787	SQFT	Construction Signs
740C000	36	SQFT	Special Construction Signs
740D000	350	Each	Channelizing Drums
740E000	600	Each	Cones (36 Inches High)
740M001	600	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	3	Each	Portable Changeable Message Sign, Type 2