

Alabama Department of Transportation
Proposal Item Summary

027. IM-1065(494)

MONTGOMERY COUNTY

Contract Time: 40 Working Days

DBE Goal Percent: 4.00

for constructing the Planing, Resurfacing, and Traffic Stripe on I-65 from Catoma Creek (MP 167.540) to north of the Fairview Avenue Interchange in Montgomery. Length 2.979 mi.

The Bracket Estimate on this project is from \$2,136,882 to \$2,611,744.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$10.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
408B001	162,400	SQYD	Micro-Milling Existing Pavement(Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
420A015	7,700	Ton	Polymer Modified Open Graded Friction Course
420B000	30,700	Gal	Open Graded Friction Course Tack Coat
424B283	150	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424B287	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range E
432A000	35,000	SQYD	High Density Mineral Bond
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 108,900.00)
701A227	6	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	13	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B063	9,558	LF	Dotted, Class 2, Type A Traffic Stripe(Lane Drop 10" Wide)
701B207	8,440	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	25	Mile	Broken Temporary Traffic Stripe
701C001	24	Mile	Solid Temporary Traffic Stripe
701F000	16,880	LF	Dotted Temporary Traffic Stripe
701F010	19,116	LF	Dotted Temporary Traffic Stripe (Lane Drop)
701G142	3,440	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	1,720	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	1,720	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G161	3,440	LF	Broken Black, Class W, Type B Traffic Stripe (5" Wide)
701H001	3,440	LF	Solid Traffic Stripe Removed (Plastic)
701H006	3,440	LF	Broken Traffic Stripe Removed (Plastic)
703A002	8,266	SQFT	Traffic Control Markings, Class 2, Type A
703B002	902	SQFT	Traffic Control Legends, Class 2, Type A
703D001	11,559	SQFT	Temporary Traffic Control Markings
705A030	815	Each	Pavement Markers, Class A-H, Type 2-C
705A031	588	Each	Pavement Markers, Class A-H, Type 1-A
705A032	123	Each	Pavement Markers, Class A-H, Type 1-B
731A001	1	Each	Traffic Counting Units, Type B
740B000	2,100	SQFT	Construction Signs
740C000	90	SQFT	Special Construction Signs
740D000	500	Each	Channelizing Drums
740E000	500	Each	Cones (36 Inches High)
740M001	500	Each	Ballast For Cone
741C010	4	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	8	Each	Portable Changeable Message Sign, Type 2