

Alabama Department of Transportation
Proposal Item Summary

032. NH-0012(567) & STPAA-HSIP-0100(500)

COVINGTON COUNTY

Contract Time: 40 Working Days

DBE Goal Percent: 6.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-12 (US-84) from the junction of SR-100 in Andalusia to west of the intersection of CR-67 (Site 1) and the Safety Widening, Planing, Resurfacing, and Traffic Stripe on SR-100 from the junction of SR-15 (East 3 Notch Street) to the junction of SR-12 (US-84) in Andalusia (Site 2). Length 4.816 mi.

The Bracket Estimate on this project is from \$2,102,145 to \$2,569,288.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$15.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C002	40	SQYD	Removing Concrete Slope Paving
206C010	252	SQYD	Removing Concrete Driveway
206D000	104	LF	Removing Pipe
206D001	1,013	LF	Removing Guardrail
206E000	2	Each	Removing Headwalls
206E008	14	Each	Removing Guardrail End Anchor (All Type)
209A000	4	Each	Mailbox Reset, Single
210A000	378	CUYD	Unclassified Excavation
210D021	290	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
212A000	268	STA	Machine Grading Shoulders
405A000	16,080	Gal	Tack Coat
407B000	21	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	137,953	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
410I000	1	Each	Smoothness Testing, Certified Inertial Profiler
424A361	11,470	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	1,639	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B650	1,557	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	150	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B663	583	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	150	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
428A001	3	Mile	Scoring Bituminous Pavement Surface
432A000	37,948	SQYD	High Density Mineral Bond
600A000	1	LS	Mobilization
630A001	956	LF	Steel Beam Guardrail, Class A, Type 2
630C001	1	Each	Guardrail End Anchor, Type 8
630C003	6	Each	Guardrail End Anchor, Type 13
630C080	7	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	1,044	CUYD	Topsoil
652A100	7	Acre	Seeding
652C000	9	Acre	Mowing
654A001	648	SQYD	Solid Sodding (Bermuda)
656A010	7	Acre	Mulching
659C002	500	SQYD	Erosion Control Product, Type S2

Item No.	Quantity	Units	Description
665A000	5 Acre		Temporary Seeding
665B001	21 Ton		Temporary Mulching
665E000	300 SQYD		Polyethylene
665G000	460 Each		Sand Bags
665J002	800 LF		Silt Fence
665O001	800 LF		Silt Fence Removal
665P005	1 Each		Inlet Protection, Stage 3 Or 4
665Q002	990 LF		Wattle
666A001	7 Acre		Pest Control Treatment
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 112,160.00)
701A227	12 Mile		Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	10 Mile		Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	7 Mile		Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2 Mile		Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	6,995 LF		Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	15 Mile		Broken Temporary Traffic Stripe
701C001	37 Mile		Solid Temporary Traffic Stripe
701D007	2 Mile		Solid Traffic Stripe Removed (Paint)
701D008	2 Mile		Solid Traffic Stripe Removed (Plastic)
701D014	2 Mile		Broken Traffic Stripe Removed (Paint)
701D015	2 Mile		Broken Traffic Stripe Removed (Plastic)
701G142	1,100 LF		Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	1,100 LF		Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	1,100 LF		Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A002	4,611 SQFT		Traffic Control Markings, Class 2, Type A
703B002	1,280 SQFT		Traffic Control Legends, Class 2, Type A
703D001	2,716 SQFT		Temporary Traffic Control Markings
703E001	137 SQFT		Temporary Traffic Control Legends
705A030	875 Each		Pavement Markers, Class A-H, Type 2-C
705A032	26 Each		Pavement Markers, Class A-H, Type 1-B
705A037	203 Each		Pavement Markers, Class A-H, Type 2-D
730H001	525 LF		Loop Wire
740B000	1,953 SQFT		Construction Signs
740C000	18 SQFT		Special Construction Signs
740D000	25 Each		Channelizing Drums
740E000	150 Each		Cones (36 Inches High)
740I002	4 Each		Warning Lights, Type B
740M001	150 Each		Ballast For Cone
740O000	1 Each		Pilot Car
741C010	2 Each		Portable Sequential Arrow And Chevron Sign Unit
742A001	2 Each		Portable Changeable Message Sign, Type 2