

Alabama Department of Transportation
Proposal Item Summary

035. NH-0038(544)

COOSA COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-38 (US-280) from the Talladega County Line to 0.563 mile east of the intersection of CR-49. Length 6.505 mi.

The Bracket Estimate on this project is from \$2,097,004 to \$2,563,004.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	1,300	Gal	Tack Coat
407B000	15	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B000	230,000	SQYD	Micro-Milling Existing Pavement(Approximately 0.00" Thru 1.00" Thick)
410H000	1	Each	Material Remixing Device
420A015	9,950	Ton	Polymer Modified Open Graded Friction Course
420B000	39,700	Gal	Open Graded Friction Course Tack Coat
424A276	700	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range E
424A279	150	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range E
424B284	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range E
424B287	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range E
430B043	100	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 118,000.00)
701A227	15	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	14	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	14	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	14,061	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	32	Mile	Broken Temporary Traffic Stripe
701C001	64	Mile	Solid Temporary Traffic Stripe
703A002	1,718	SQFT	Traffic Control Markings, Class 2, Type A
703B002	1,711	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,074	SQFT	Temporary Traffic Control Markings
705A030	850	Each	Pavement Markers, Class A-H, Type 2-C
705A037	100	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,255	SQFT	Construction Signs
740E000	300	Each	Cones (36 Inches High)
740M001	300	Each	Ballast For Cone
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	1	Each	Portable Changeable Message Sign, Type 2