

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**036. NH-0042(536)**

**MOBILE COUNTY**

Contract Time: 100 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-42 (US-98) from the junction of Magnolia Grove Parkway to the junction of Stimpson Lane in Mobile. Length 5.017 mi.

The Bracket Estimate on this project is from \$2,208,128 to \$2,698,824.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$10.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C000	66	SQYD	Removing Concrete Sidewalk
206D000	52	LF	Removing Pipe
206D003	90	LF	Removing Curb And Gutter
206E001	2	Each	Removing Inlets
206E008	4	Each	Removing Guardrail End Anchor (All Type)
212A000	18	STA	Machine Grading Shoulders
405A000	19,501	Gal	Tack Coat
407B000	21	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	195,002	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	20,523	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A366	50	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	946	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
530A001	4	LF	18" Roadway Pipe (Class 3 R.C.)
532A032	52	LF	18" Slotted Drain Pipe
533A097	4	LF	15" Storm Sewer Pipe (Class 3 R.C.)
533A099	16	LF	24" Storm Sewer Pipe (Class 3 R.C.)
600A000	1	LS	Mobilization
618A000	99	SQYD	Concrete Sidewalk, 4" Thick
620A000	1	CUYD	Minor Structure Concrete
621C036	2	Each	Inlets, Type S1 Or S3 (1 Wing) (Modified)
621D015	4	Each	Inlet Units, Type S1 Or S3
623C000	90	LF	Combination Curb & Gutter, Type C
630A001	712	LF	Steel Beam Guardrail, Class A, Type 2
630C001	2	Each	Guardrail End Anchor, Type 8
630C080	2	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	50	CUYD	Topsoil
652A100	1	Acre	Seeding
652C000	1	Acre	Mowing
654A001	995	SQYD	Solid Sodding (Bermuda)
656A010	1	Acre	Mulching
665J002	50	LF	Silt Fence
665O001	50	LF	Silt Fence Removal
665Q002	25	LF	Wattle
666A001	1	Acre	Pest Control Treatment

Item No.	Quantity	Units	Description
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 117,000.00)
701A227	11	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	11	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	11	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	11	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B063	613	LF	Dotted, Class 2, Type A Traffic Stripe(Lane Drop 10" Wide)
701B207	1,990	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	32	Mile	Broken Temporary Traffic Stripe
701C001	32	Mile	Solid Temporary Traffic Stripe
701G142	732	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	488	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	488	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	976	LF	Solid Traffic Stripe Removed (Plastic)
701H006	732	LF	Broken Traffic Stripe Removed (Plastic)
703A002	5,017	SQFT	Traffic Control Markings, Class 2, Type A
703A011	33	SQFT	Traffic Control Markings, Class W, Type A
703B002	1,178	SQFT	Traffic Control Legends, Class 2, Type A
703B011	45	SQFT	Traffic Control Legends, Class W, Type A
703C001	78	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Plastic)
703D001	1,554	SQFT	Temporary Traffic Control Markings
703E001	819	SQFT	Temporary Traffic Control Legends
705A030	821	Each	Pavement Markers, Class A-H, Type 2-C
705A031	426	Each	Pavement Markers, Class A-H, Type 1-A
705A032	174	Each	Pavement Markers, Class A-H, Type 1-B
705A037	1,363	Each	Pavement Markers, Class A-H, Type 2-D
705A038	144	Each	Pavement Markers, Class A-H, Type 2-E
707F002	13	Each	Flexible Delineator Post with Base, White
730H001	19,925	LF	Loop Wire
730L005	850	LF	2", Non-Metallic, Conduit
740B000	892	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit