

Alabama Department of Transportation
Proposal Item Summary

038. NH-0163(504)

MOBILE COUNTY

Contract Time: 75 Working Days

DBE Goal Percent: 4.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-163 from the south end of the Dog River Bridge (MP 2.525) to the south end of the I-10 Overpass (MP 8.562) in Mobile. Length 6.036 mi.

The Bracket Estimate on this project is from \$2,215,333 to \$2,707,629.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$14.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	245	SQYD	Removing Concrete Sidewalk
206D003	155	LF	Removing Curb And Gutter
212A000	31	STA	Machine Grading Shoulders
405A000	20,443	Gal	Tack Coat
407B000	25	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	204,423	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	19,836	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A366	500	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	607	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
618A000	244	SQYD	Concrete Sidewalk, 4" Thick
623C000	53	LF	Combination Curb & Gutter, Type C
650A000	25	CUYD	Topsoil
652A100	1	Acre	Seeding
654A001	200	SQYD	Solid Sodding (Bermuda)
656A010	1	Acre	Mulching
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
665Q002	100	LF	Wattle
666A001	1	Acre	Pest Control Treatment
674A000	750	LF	Construction Safety Fence
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 125,000.00)
701A108	2	Mile	Broken Black, Class W, Type B Traffic Stripe (5" Wide)
701A227	16	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	13	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	7	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	6	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,895	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	21	Mile	Broken Temporary Traffic Stripe
701C001	21	Mile	Solid Temporary Traffic Stripe
701G142	7,361	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	8,997	LF	Solid White, Class W, Type A Traffic Stripe (5" Wide)
701G150	546	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	17,315	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701H002	25,424	LF	Solid Traffic Stripe Removed (Tape)
701H007	15,810	LF	Broken Traffic Stripe Removed (Tape)
703A002	8,118	SQFT	Traffic Control Markings, Class 2, Type A
703B002	1,884	SQFT	Traffic Control Legends, Class 2, Type A
703D001	7,951	SQFT	Temporary Traffic Control Markings
703E001	1,884	SQFT	Temporary Traffic Control Legends
705A007	553	Each	Pavement Markers, Class B, Type 1-A
705A030	1,902	Each	Pavement Markers, Class A-H, Type 2-C
705A032	70	Each	Pavement Markers, Class A-H, Type 1-B
705A037	595	Each	Pavement Markers, Class A-H, Type 2-D
705A038	184	Each	Pavement Markers, Class A-H, Type 2-E
710A160	72	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710B001	196	LF	Roadway Sign Post (#3 "U" Channel Galvanized Steel)
730H001	14,500	LF	Loop Wire
730L005	700	LF	2", Non-Metallic, Conduit
740B000	1,020	SQFT	Construction Signs
740D000	250	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2