

Alabama Department of Transportation
Proposal Item Summary

047. STPAA-0015(533)

BULLOCK COUNTY

Contract Time: 55 Working Days

DBE Goal Percent: 4.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-15 (US-29) from the junction of SR-6 (US-82) to the Macon County Line. Length 6.217 mi.

The Bracket Estimate on this project is from \$2,422,604 to \$2,960,960.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D002	346 LF		Removing Curb
210D011	750 CUYD		Borrow Excavation (A4 Or Better)
212A000	540 STA		Machine Grading Shoulders
305B077	500 Ton		Crushed Aggregate, Section 825, For Miscellaneous Use
401A004	27,400 SQYD		Bituminous Treatment E
401B107	84,800 SQYD		Bituminous Treatment KG (With Polymer Additive)
405A000	7,000 Gal		Tack Coat
407B000	8 Mile		Joint Sealant For Hot Mix Asphalt Pavement
408A053	120,000 SQYD		Planing Existing Pavement (Approximately 2.10" Thru 3.0" Thick)
410H000	1 Each		Material Remixing Device
410I000	1 Each		Smoothness Testing, Certified Inertial Profiler
424A356	6,455 Ton		Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A359	500 Ton		Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B650	12,900 Ton		Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	1,000 Ton		Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500 Ton		Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B693	10 Ton		Superpave Bituminous Concrete Lower Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	11 Mile		Scoring Bituminous Pavement Surface
600A000	1 LS		Mobilization
610E000	175 SQYD		Tied Concrete Block Mat
623B000	216 LF		Concrete Curb, Type N
650A000	1,500 CUYD		Topsoil
652A100	3 Acre		Seeding
652C000	3 Acre		Mowing
654A000	250 SQYD		Solid Sodding
656A010	3 Acre		Mulching
659C002	500 SQYD		Erosion Control Product, Type S2
665F000	100 Each		Hay Bales
665G000	100 Each		Sand Bags
665J002	500 LF		Silt Fence
665O001	500 LF		Silt Fence Removal
666A001	3 Acre		Pest Control Treatment
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 136,400.00)
701A227	13 Mile		Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	8 Mile		Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701A239	1 Mile		Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	4 Mile		Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,270 LF		Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	5 Mile		Broken Temporary Traffic Stripe
701C001	63 Mile		Solid Temporary Traffic Stripe
701G146	748 LF		Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	374 LF		Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G252	900 LF		Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
701H001	748 LF		Solid Traffic Stripe Removed (Plastic)
701H006	374 LF		Broken Traffic Stripe Removed (Plastic)
703A002	2,100 SQFT		Traffic Control Markings, Class 2, Type A
703B002	135 SQFT		Traffic Control Legends, Class 2, Type A
703D001	900 SQFT		Temporary Traffic Control Markings
705A030	150 Each		Pavement Markers, Class A-H, Type 2-C
705A031	60 Each		Pavement Markers, Class A-H, Type 1-A
705A032	530 Each		Pavement Markers, Class A-H, Type 1-B
705A037	548 Each		Pavement Markers, Class A-H, Type 2-D
705A038	175 Each		Pavement Markers, Class A-H, Type 2-E
740B000	1,024 SQFT		Construction Signs
740D000	100 Each		Channelizing Drums
740E000	200 Each		Cones (36 Inches High)
740M001	200 Each		Ballast For Cone
740O000	1 Each		Pilot Car
741C010	2 Each		Portable Sequential Arrow And Chevron Sign Unit