

**Alabama Department of Transportation
Proposal Item Summary**

051. STPAA-0285(500) & 99-807-036-000-901

BARBOUR COUNTY

Contract Time: 30 Working Days

for constructing the Preventative Maintenance (High Performance Chip Seal) and Traffic Stripe on State Park Road and SR-285 from SR-1 (US-431) to SR-165 in Eufaula. Length 2.273 mi.

The Bracket Estimate on this project is from \$263,470 to \$322,019.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
209A000	7	Each	Mailbox Reset, Single
209A002	1	Each	Mailbox Reset, Multiple
405A000	50	Gal	Tack Coat
424B640	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B700	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range A/B
434A000	34,205	SQYD	High Performance Chip Seal
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 28,000.00)
701A227	6	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	1	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	280	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	12	Mile	Solid Temporary Traffic Stripe
701D007	2	Mile	Solid Traffic Stripe Removed (Paint)
701D008	2	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	2	Mile	Broken Traffic Stripe Removed (Paint)
701D015	2	Mile	Broken Traffic Stripe Removed (Plastic)
701G146	180	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	90	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	90	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A002	1,763	SQFT	Traffic Control Markings, Class 2, Type A
703B002	146	SQFT	Traffic Control Legends, Class 2, Type A
703C001	1,909	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Plastic)
703D001	672	SQFT	Temporary Traffic Control Markings
705A030	200	Each	Pavement Markers, Class A-H, Type 2-C
705A032	40	Each	Pavement Markers, Class A-H, Type 1-B
705A037	150	Each	Pavement Markers, Class A-H, Type 2-D
740B000	820	SQFT	Construction Signs
740C000	27	SQFT	Special Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car