

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**055. STPAA-HSIP-0073(501)**

**JACKSON COUNTY**

Contract Time: 45 Working Days

DBE Goal Percent: 6.00

for constructing the Resurfacing (Scrub Seal), Safety Installation of High Friction Surface Treatment, Guardrail Replacement, and Traffic Stripe on SR-73 from the junction of SR-71 to the Tennessee State Line. Length 11.220 mi.

The Bracket Estimate on this project is from \$2,267,846 to \$2,771,812.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206D001	380	LF	Removing Guardrail
206E008	2	Each	Removing Guardrail End Anchor (All Type)
206E043	1,425	Each	Removing Raised Pavement Markers
209A000	48	Each	Mailbox Reset, Single
405A000	15,925	Gal	Tack Coat
407B000	12	Mile	Joint Sealant For Hot Mix Asphalt Pavement
410H000	1	Each	Material Remixing Device
424A360	13,935	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	517	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424C364	600	Ton	Superpave Bituminous Concrete Base Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	23	Mile	Scoring Bituminous Pavement Surface
430B043	5,865	Ton	Aggregate Surfacing (1" Down, Crusher Run)
431A000	3,286	SQYD	Pressure Cleaning
431B000	3,286	SQYD	Thin Polymer Overlay
433A000	184,308	SQYD	Scrub Seal
600A000	1	LS	Mobilization
630A001	380	LF	Steel Beam Guardrail, Class A, Type 2
630C080	2	Each	Guardrail End Anchor, Type 20 Series (MASH)
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 133,000.00)
701A227	23	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	18	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	41	Mile	Solid Temporary Traffic Stripe
701H001	216,480	LF	Solid Traffic Stripe Removed (Plastic)
701H006	21,120	LF	Broken Traffic Stripe Removed (Plastic)
703A002	436	SQFT	Traffic Control Markings, Class 2, Type A
703B002	266	SQFT	Traffic Control Legends, Class 2, Type A
703C001	702	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Plastic)
703D001	436	SQFT	Temporary Traffic Control Markings
703E001	266	SQFT	Temporary Traffic Control Legends
705A032	152	Each	Pavement Markers, Class A-H, Type 1-B
705A037	1,273	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,122	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740I002	2	Each	Warning Lights, Type B

Item No.	Quantity	Units	Description
740M001	200 Each	Ballast For Cone	