

Alabama Department of Transportation
Proposal Item Summary

059. STPNU-1418(250)

CLAY COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Resurfacing and Traffic Stripe on CR-130 (Idaho Road) from the Talladega County Line to the junction of SR-77. Length 6.707 mi.

The Bracket Estimate on this project is from \$866,397 to \$1,058,929.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E019	1	Each	Removing Guardrail End Anchor (Type 10)
401B108	78,482	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	7,870	Gal	Tack Coat
407B000	7	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A346	6,718	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	450	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	2,287	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630C070	1	Each	Guardrail End Anchor, Type 10 Series
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 46,500.00)
701A231	14	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	12	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	23	Mile	Solid Temporary Traffic Stripe
703A002	388	SQFT	Traffic Control Markings, Class 2, Type A
705A032	126	Each	Pavement Markers, Class A-H, Type 1-B
705A037	740	Each	Pavement Markers, Class A-H, Type 2-D
740B000	353	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car