

Alabama Department of Transportation
Proposal Item Summary

041. STPNU-3118(250)

GENEVA COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Resurfacing and Traffic Stripe on CR-33 from the Florida State Line to the junction of SR-27 southwest of Geneva. Length 2.532 mi.

The Bracket Estimate on this project is from \$447,424 to \$546,851.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
210D021	185	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
212A000	268	STA	Machine Grading Shoulders
401A006	32,685	SQYD	Bituminous Treatment G
405A000	1,790	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
410H000	1	Each	Material Remixing Device
424A340	2,825	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
652A100	5	Acre	Seeding
652C000	5	Acre	Mowing
656A010	5	Acre	Mulching
665F000	70	Each	Hay Bales
665J002	840	LF	Silt Fence
665O001	840	LF	Silt Fence Removal
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 24,000.00)
701A231	6	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	2	Mile	Broken Temporary Traffic Stripe
701C001	4	Mile	Solid Temporary Traffic Stripe
703A002	180	SQFT	Traffic Control Markings, Class 2, Type A
703D002	180	SQFT	Temporary Traffic Control Markings (Paint)
705A032	89	Each	Pavement Markers, Class A-H, Type 1-B
705A037	258	Each	Pavement Markers, Class A-H, Type 2-D
740B000	369	SQFT	Construction Signs
740O000	1	Each	Pilot Car