

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**044. STPNU-HSIP-0069(558)**

**CLARKE COUNTY**

Contract Time: 45 Working Days

DBE Goal Percent: 4.00

for constructing the Safety Widening, Planing, Resurfacing, and Traffic Stripe on SR-69 from the junction of SR-177 in Jackson to 0.608 mile north of the junction of CR-23 (Salt Works Road) northwest of Jackson. Length 6.928 mi.

The Bracket Estimate on this project is from \$1,328,233 to \$1,623,396.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
212A000	657 STA		Machine Grading Shoulders
405A000	13,356 Gal		Tack Coat
407B000	8 Mile		Joint Sealant For Hot Mix Asphalt Pavement
408B000	106,327 SQYD		Micro-Milling Existing Pavement(Approximately 0.00" Thru 1.00" Thick)
410H000	1 Each		Material Remixing Device
424A336	8,300 Ton		Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range A/B
424A339	552 Ton		Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	100 Ton		Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B700	200 Ton		Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range A/B
424C350	2,557 Ton		Superpave Bituminous Concrete Base Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	14 Mile		Scoring Bituminous Pavement Surface
430B043	780 Ton		Aggregate Surfacing (1" Down, Crusher Run)
600A000	1 LS		Mobilization
614A000	32 CUYD		Slope Paving
623B000	117 LF		Concrete Curb, Type N
623B001	22 LF		Concrete Curb, Type N Special
650A000	1,500 CUYD		Topsoil
652A100	8 Acre		Seeding
652C000	34 Acre		Mowing
656A010	8 Acre		Mulching
665B001	24 Ton		Temporary Mulching
665J002	300 LF		Silt Fence
665O001	300 LF		Silt Fence Removal
665Q002	300 LF		Wattle
666A001	8 Acre		Pest Control Treatment
680A001	1 LS		Geometric Controls
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 20,000.00)
701A227	15 Mile		Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	13 Mile		Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3 Mile		Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	191 LF		Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	6 Mile		Broken Temporary Traffic Stripe
701C001	54 Mile		Solid Temporary Traffic Stripe
701G146	824 LF		Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	824 LF		Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701H002	1,648	LF	Solid Traffic Stripe Removed (Tape)
703A002	817	SQFT	Traffic Control Markings, Class 2, Type A
703B002	429	SQFT	Traffic Control Legends, Class 2, Type A
703D000	580	SQFT	Temporary Traffic Control Markings (Tape)
703E000	714	SQFT	Temporary Traffic Control Legends (Tape)
705A030	263	Each	Pavement Markers, Class A-H, Type 2-C
705A032	148	Each	Pavement Markers, Class A-H, Type 1-B
705A037	844	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,028	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740I002	4	Each	Warning Lights, Type B
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car