

Alabama Department of Transportation
Proposal Item Summary

045. STPNU-HSIP-0114(503)

MARENGO COUNTY

Contract Time: 40 Working Days

DBE Goal Percent: 3.00

for constructing the Safety Widening, Planing, Resurfacing, and Traffic Stripe on SR-114 from the Choctaw County Line to the junction of SR-69 in Myrtlewood. Length 4.792 mi.

The Bracket Estimate on this project is from \$1,097,873 to \$1,341,845.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
212A000	238 STA		Machine Grading Shoulders
401B108	75,500 SQYD		Bituminous Treatment G (With Polymer Additive)
405A000	4,000 Gal		Tack Coat
407B000	5 Mile		Joint Sealant For Hot Mix Asphalt Pavement
408A052	81,322 SQYD		Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1 Each		Material Remixing Device
424A341	7,400 Ton		Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424A350	251 Ton		Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	150 Ton		Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B643	250 Ton		Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424C350	963 Ton		Superpave Bituminous Concrete Base Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	15 Mile		Scoring Bituminous Pavement Surface
430B043	150 Ton		Aggregate Surfacing (1" Down, Crusher Run)
600A000	1 LS		Mobilization
650A000	2,502 CUYD		Topsoil
652A100	4 Acre		Seeding
652C000	12 Acre		Mowing
656A010	4 Acre		Mulching
665B001	36 Ton		Temporary Mulching
665J002	500 LF		Silt Fence
665O001	500 LF		Silt Fence Removal
665Q002	300 LF		Wattle
666A001	4 Acre		Pest Control Treatment
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 62,000.00)
701A227	11 Mile		Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	5 Mile		Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	4 Mile		Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	291 LF		Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	13 Mile		Broken Temporary Traffic Stripe
701C001	39 Mile		Solid Temporary Traffic Stripe
703A002	1,537 SQFT		Traffic Control Markings, Class 2, Type A
703B002	104 SQFT		Traffic Control Legends, Class 2, Type A
703D001	222 SQFT		Temporary Traffic Control Markings
703E001	167 SQFT		Temporary Traffic Control Legends
705A030	171 Each		Pavement Markers, Class A-H, Type 2-C

Item No.	Quantity	Units	Description
705A032	46	Each	Pavement Markers, Class A-H, Type 1-B
705A037	430	Each	Pavement Markers, Class A-H, Type 2-D
740B000	628	SQFT	Construction Signs
740D000	25	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car