

Alabama Department of Transportation
Proposal Item Summary

054. 99-406-011-065-801

AUTAUGA COUNTY

Contract Time: 45 Working Days

for constructing the Slope Repair (Front Slope Failure) on I-65 at MP 190.400 (Southbound Roadway) northwest of Montgomery. Length 0.435 mi.

The Bracket Estimate on this project is from \$746,247 to \$912,080.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$18.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1 LS		Clearing And Grubbing (Maximum Allowable Bid \$ 75,000.00 Per Acre) (Approximately 1 Acre)
206C003	390 SQYD		Removing Concrete Flumes
206D000	167 LF		Removing Pipe
206D001	2,232 LF		Removing Guardrail
206D028	460 LF		Removing Steel Sheet Piling
206E000	1 Each		Removing Headwalls
206E008	2 Each		Removing Guardrail End Anchor (All Type)
206E042	3 Each		Removing Inlets (Partial)
210A000	2,334 CUYD		Unclassified Excavation
210D021	1,000 CUYD		Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
214A000	118 CUYD		Structure Excavation
214B001	43 CUYD		Foundation Backfill, Commercial
219A000	3,509 Ton		Rock Buttress For Landslide Correction
219C003	2,655 SQYD		Special Filter Blanket, Geotextile
305B077	30 Ton		Crushed Aggregate, Section 825, For Miscellaneous Use
530A201	222 LF		18" Roadway Pipe (14 Gauge C.C.S.P.I.)
600A000	1 LS		Mobilization
610C001	4,190 Ton		Loose Riprap, Class 2
610D003	3,519 SQYD		Filter Blanket, Geotextile
619A002	3 Each		18" Roadway Pipe End Treatment, Class 1
620A000	2 CUYD		Minor Structure Concrete
621A058	3 Each		Junction Boxes, Type 3 (Modified)
630A001	2,232 LF		Steel Beam Guardrail, Class A, Type 2
630C001	1 Each		Guardrail End Anchor, Type 8
630C080	1 Each		Guardrail End Anchor, Type 20 Series (MASH)
635A001	2,110 LF		Woven Wire Fence (Metal Posts)
652A100	1 Acre		Seeding
656A010	1 Acre		Mulching
665J002	100 LF		Silt Fence
665N000	50 Ton		Temporary Coarse Aggregate,ALDOT Number 1
665O001	100 LF		Silt Fence Removal
680A001	1 LS		Geometric Controls
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 62,000.00)
740B000	516 SQFT		Construction Signs
740D000	20 Each		Channelizing Drums
740E000	50 Each		Cones (36 Inches High)
740M001	50 Each		Ballast For Cone
741C010	1 Each		Portable Sequential Arrow And Chevron Sign Unit
742A001	1 Each		Portable Changeable Message Sign, Type 2