

**Alabama Department of Transportation
Proposal Item Summary**

001. IMF-I085(317)

CHAMBERS COUNTY

Contract Time: 4/16/2021 Completion Date

DBE Goal Percent: 5.00

for constructing the Welcome Center Replacement on I-85 at the Georgia State Line. Length 0.470 mi.

The Bracket Estimate on this project is from \$11,165,951 to \$13,647,274.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$66.00 per set.

The Principal Items of work are approximately as follows:

A MANDATORY pre-bid conference is scheduled for 10:00 a.m. on Thursday, August 8, 2019, at the Alabama Department of Transportation - Alexander City Area Office, 240 Highway 280, Alexander City, AL 35010 Any qualified bidder wishing to bid this proposal is required to have a company representative present at this MANDATORY pre-bid conference. Proposals issued to bidders who fail to attend the MANDATORY pre-bid conference and/or register their attendance will be voided and their bids will not be received nor considered.

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 12 Acres)
201B001	4	Acre	Selective Clearing
205A001	1	Each	Removal Of Structures, Structure No. 1
205A002	1	Each	Removal Of Structures, Structure No. 2
205A003	1	Each	Removal Of Structures, Structure No. 3
205B001	1	Each	Relocation Of Structures, Structure No. 4
206C000	2,174	SQYD	Removing Concrete Sidewalk
206C021	14	SQYD	Removing Concrete Steps
206D000	3,068	LF	Removing Pipe
206D002	7,220	LF	Removing Curb
206D011	100	LF	Removing Fence
206E000	3	Each	Removing Headwalls
206E001	14	Each	Removing Inlets
206E003	1	Each	Removing Manholes
206E070	1	Each	Removing Sanitary Dumping Bay
210A000	4,479	CUYD	Unclassified Excavation
210D001	115	CUYD	Borrow Excavation (Loose Truckbed Measurement)
210D025	5,044	CUYD	Borrow Excavation (Improved Roadbed)
210D101	1,037	CUYD	Borrow Excavation (Sand Fill, Complete In Place)
210F002	1,305	Ton	Borrow Excavation (Underwater Backfill) (ALDOT #57)
214A000	1,713	CUYD	Structure Excavation
214B001	1,237	CUYD	Foundation Backfill, Commercial
230A000	20	RBST	Roadbed Processing
260A001	50	CUYD	Cement Mortar Flowable Backfill, Mix 2
301A012	11,400	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	10,700	SQYD	Bituminous Treatment A
405A000	3,200	Gal	Tack Coat
407B000	1	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	10,410	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A280	2,241	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424B280	1,840	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range E
424B580	6,343	Ton	Superpave Bituminous Concrete Lower Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range E
424B585	100	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range E

Item No.	Quantity	Units	Description
430B043	100	Ton	Aggregate Surfacing (1" Down, Crusher Run)
533A098	1,137	LF	18" Storm Sewer Pipe (Class 3 R.C.)
533A099	77	LF	24" Storm Sewer Pipe (Class 3 R.C.)
533A100	41	LF	30" Storm Sewer Pipe (Class 3 R.C.)
533A348	24	LF	18" Storm Sewer Pipe (Class 3 R.C.) (Extension)
533B100	98	LF	36" Span, 23" Rise Storm Sewer Pipe (Class 3 R.C.)
600A000	1	LS	Mobilization
601A000	1	Each	Furnishing Base, Soil And Structure Laboratories
602A000	5	Each	Right Of Way Markers
608A000	6,521	SQYD	Separation Geotextile
610D003	650	SQYD	Filter Blanket, Geotextile
618A000	1,106	SQYD	Concrete Sidewalk, 4" Thick
618A001	789	SQYD	Concrete Sidewalk, 6" Thick
618B005	119	SQYD	Concrete Driveway, 10" Thick (Includes Wire Mesh)
619A101	1	Each	18" Side Drain Pipe End Treatment, Class 1
619A102	1	Each	24" Side Drain Pipe End Treatment, Class 1
619A103	2	Each	30" Side Drain Pipe End Treatment, Class 1
620A000	4	CUYD	Minor Structure Concrete
621A011	4	Each	Junction Boxes, Type 1 Or 1P
621C015	9	Each	Inlets, Type S1 Or S3 (1 Wing)
621C017	1	Each	Inlets, Type S1 Or S3 (2 Wing)
621C109	6	Each	Inlets, Type PD
621D015	2	Each	Inlet Units, Type S1 Or S3
621D109	4	Each	Inlet Units, Type PD
623B002	1,462	LF	Concrete Curb, Type A
623C000	4,082	LF	Combination Curb & Gutter, Type C
634A002	2,270	LF	Industrial Fence, 6 Feet High
634D004	1	Each	Gate, 14 Feet Wide, Complete With Fittings (Without Barbed Wire)
641A562	640	LF	3/4 Inch P.V.C. Water Service Line Laid
641A564	190	LF	1 Inch P.V.C. Water Service Line Laid
641A568	700	LF	2 Inch P.V.C. Water Service Line Laid
641A570	91	LF	3 Inch P.V.C. Water Service Line Laid
641A610	2,565	LF	4 Inch Ductile Iron Water Main Laid
641A612	2,315	LF	6 Inch Ductile Iron Water Main Laid
641C500	2,000	LB	Ductile Iron Fittings
641D500	1	Each	Fire Hydrant
641J504	2	Each	3/4" Gate Valve With Box
641J506	1	Each	1 Inch Gate Valve With Box
641J510	1	Each	2 Inch Gate Valve With Box
641J512	1	Each	3 Inch Gate Valve With Box
641J514	7	Each	4 Inch Gate Valve With Box
641J516	4	Each	6 Inch Gate Valve With Box
641L500	30	CUYD	Concrete for Water Mains (Thrust Blocks)
641O518	1	Each	8 Inch x 6 Inch Tapping Valve And Sleeve
641Q535	1	Each	6 Inch Water Meter And Box Set
641V100	2	Each	Double Check Valve Assembly with Vault
645A506	131	LF	4 Inch Ductile Iron Sanitary Sewer Gravity Pipe Laid
645A508	33	LF	6 Inch Ductile Iron Sanitary Sewer Gravity Pipe Laid
645A510	994	LF	8 Inch Ductile Iron Sanitary Sewer Gravity Pipe Laid
645A650	161	LF	4 Inch P.V.C. Sanitary Sewer Force Main Pipe Laid
645G510	2	Each	4 Inch Sanitary Sewer Lateral Cleanout
645H540	1	Each	60 Inch Manhole
645M500	5	Each	Connection To Existing Manhole
649A520	40	LF	6 Inch Steel Encasement Pipe, Type 1 Installation
649A535	65	LF	12 Inch Steel Encasement Pipe, Type 1 Installation

Item No.	Quantity	Units	Description
650A000	1,037	CUYD	Topsoil
650B000	2,663	CUYD	Topsoil From Stockpiles
652A100	14	Acre	Seeding
654A000	3,106	SQYD	Solid Sodding
654A005	9,680	SQYD	Solid Sodding (Emerald Zoysia)
656A010	14	Acre	Mulching
659C000	257	SQYD	Erosion Control Product, Type S4
660C062	581	Each	Shrubs, Juniperus Sargentii (Green Sargent Juniper)
660C251	639	Each	Shrubs, Lantana Miss Huff (Lantana Carmara "Miss Huff")
660C252	84	Each	Shrubs, Japanese Prostate Plum Yew (Cephalotaxus Harringtonia "Prostrata")
660C253	1,354	Each	Shrubs, Coreopsis Sunshine Superman (Pubescenes "Sunshine Superman")
660C254	287	Each	Shrubs, Autumn Ember Azelea (Rhododendron "Ember")
660C255	162	Each	Shrubs, Autumn Bravo Azalea (Rhododendron "Bravo")
660D152	2	Each	Trees, Lagerstroemia Indica X Fauriei 'Natchez' (Natchez Crapeyrtle)
660J000	195	CUYD	Plant Mulch
663B000	1,200	CUYD	Tree Root Protection Material
665A000	8	Acre	Temporary Seeding
665B001	72	Ton	Temporary Mulching
665E000	600	SQYD	Polyethylene
665G000	300	Each	Sand Bags
665I000	150	Ton	Temporary Riprap, Class 2
665J002	3,910	LF	Silt Fence
665K000	117	CUYD	Drainage Sump Excavation
665N000	300	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665O001	3,910	LF	Silt Fence Removal
665P005	27	Each	Inlet Protection, Stage 3 Or 4
665Q002	2,000	LF	Wattle
665R000	100	LF	Silt Dikes
666A001	3	Acre	Pest Control Treatment
672C100	24	Each	Flocculant Application, Ditch Check
674A000	1,000	LF	Construction Safety Fence
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 525,000.00)
703A002	10,969	SQFT	Traffic Control Markings, Class 2, Type A
703H000	408	SQFT	Specialty Traffic Control Markings
705A031	32	Each	Pavement Markers, Class A-H, Type 1-A
710A160	250	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710A165	46	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background, Fluorescent)
710A170	80	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)
710B021	741	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2 ", 14 Ga Square Tubular Steel)
710C000	1	LS	Removal Of Existing Roadway Signs
711A000	1	LS	Roadway Sign Relocation
726A000	750	LF	Portable Concrete Safety Barriers, Type 6
726D020	5	Each	Portable Impact Attenuator Assembly (Unidirectional,TL-2)
740B000	182	SQFT	Construction Signs
740C000	84	SQFT	Special Construction Signs
740E000	50	Each	Cones (36 Inches High)
740F002	4	Each	Barricades, Type III
740I002	8	Each	Warning Lights, Type B
740M001	50	Each	Ballast For Cone
742A001	1	Each	Portable Changeable Message Sign, Type 2
750Z220	1	LS	Roadway Lighting
770L004	1	Each	Picnic Tables (Relocation)
770L005	2	Each	Bollard,Complete In Place
770M001	6	Each	Outdoor Shelters (Renovation)

Item No.	Quantity	Units	Description
770M002	1	Each	Outdoor Shelters (Relocation)
770P000	1	Each	Sanitary Dumping Bay
771E000	1	LS	Pumping Station
780A000	1	LS	Welcome Center Building (Including All Appurtenances Shown On Plans)
792A000	7	Each	Site Furnishings (Benches)
792A001	28	Each	Site Furnishings (Garbage Depositories)
792A002	5	Each	Site Furnishings (Pet Stations)
792A003	1	Each	Site Furnishings (35 Foot Flag Pole And All Components For A Working Assembly)
792A004	2	Each	Site Furnishings (30 Foot Flag Pole And All Components For A Working Assembly)
792A005	7	Each	Site Furnishings (Ash Urn Placed As Directed By Engineer)
999 000	1,760	HOUR	Trainee Hours At 80 Cents Per Hour