

**Alabama Department of Transportation
Proposal Item Summary**

007. DPTA-5419(250)

PICKENS COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on CR-63 from 0.900 mile south of the junction of Snider Road to the junction of SR-6 (US-82) south of Gordo. Length 6.999 mi.

The Bracket Estimate on this project is from \$960,532 to \$1,173,983.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	9,000	Gal	Tack Coat
407B000	7	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A051	3,050	SQYD	Planing Existing Pavement (Approximately 0.00" Thru 1.0" Thick)
424A340	7,300	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	350	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	600	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	1,400	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A001	100	LF	Steel Beam Guardrail, Class A, Type 2
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 51,000.00)
701A030	14	Mile	Solid White, Class 2T, Type A Traffic Stripe
701A034	11	Mile	Solid Yellow, Class 2T, Type A Traffic Stripe
701A044	3	Mile	Broken Yellow, Class 2T, Type A Traffic Stripe
701C000	3	Mile	Broken Temporary Traffic Stripe
701C001	11	Mile	Solid Temporary Traffic Stripe
703A004	204	SQFT	Traffic Control Markings, Class 2T, Type A
705A032	146	Each	Pavement Markers, Class A-H, Type 1-B
705A037	735	Each	Pavement Markers, Class A-H, Type 2-D
740B000	614	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car