

**Alabama Department of Transportation
Proposal Item Summary**

015. HRRR-1619(250)

COFFEE COUNTY

Contract Time: 20 Working Days

for constructing the Guardrail Installations on CR-644 over Tight Eye Creek (Site 1) and on CR-342 over Big Creek (Site 2). Length 0.166 mi.

The Bracket Estimate on this project is from \$111,774 to \$136,613.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	652	LF	Removing Guardrail
600A000	1	LS	Mobilization
630A001	450	LF	Steel Beam Guardrail, Class A, Type 2
630A004	612	LF	Steel Beam Guardrail, Class B, Type 2
630C022	8	Each	Guardrail End Anchor, Type Special
630C080	8	Each	Guardrail End Anchor, Type 20 Series (MASH)
740B000	192	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone