

**Alabama Department of Transportation
Proposal Item Summary**

022. HRRR-6019(250)

SUMTER COUNTY

Contract Time: 40 Working Days

for constructing the Guardrail Installations on CR-12 over Potts and Sanusi Creeks (Sites 1 and 2); on CR-42 over Cotahaga Creek (Sites 3 and 4); and on CR-10 over Thornton and Kinterbish Creeks (Sites 5 and 6). Length 0.227 mi.

The Bracket Estimate on this project is from \$249,498 to \$304,942.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
210D021	2,900	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
600A000	1	LS	Mobilization
630A001	350	LF	Steel Beam Guardrail, Class A, Type 2
630C022	12	Each	Guardrail End Anchor, Type Special
630C080	24	Each	Guardrail End Anchor, Type 20 Series (MASH)
652A100	2	Acre	Seeding
656A010	2	Acre	Mulching
659C002	7,560	SQYD	Erosion Control Product, Type S2
665J002	1,300	LF	Silt Fence
665O001	1,300	LF	Silt Fence Removal
665Q002	1,300	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 7,900.00)
740B000	96	SQFT	Construction Signs
740E000	20	Each	Cones (36 Inches High)
740M001	20	Each	Ballast For Cone