

**Alabama Department of Transportation
Proposal Item Summary**

028. STPAA-5719(250)

RUSSELL COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Resurfacing and Traffic Stripe on CR-49 (Rutherford Road) from the Barbour County Line to the Hurtsboro City Limits. Length 9.429 mi.

The Bracket Estimate on this project is from \$1,468,894 to \$1,795,315.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	322	LF	Removing Guardrail
210D001	500	CUYD	Borrow Excavation (Loose Truckbed Measurement)
401B108	110,645	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	1,550	Gal	Tack Coat
407B000	10	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A340	9,380	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	2,250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	750	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	2,670	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A004	273	LF	Steel Beam Guardrail, Class B, Type 2
630C022	4	Each	Guardrail End Anchor, Type Special
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
665F000	50	Each	Hay Bales
665J002	550	LF	Silt Fence
665O001	550	LF	Silt Fence Removal
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 78,800.00)
701A231	19	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	8	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	9	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	17	Mile	Broken Temporary Traffic Stripe
701C001	15	Mile	Solid Temporary Traffic Stripe
705A032	325	Each	Pavement Markers, Class A-H, Type 1-B
705A037	715	Each	Pavement Markers, Class A-H, Type 2-D
740B000	177	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car