

**Alabama Department of Transportation
Proposal Item Summary**

029. STPAA-5818(250)

ST. AND CLAIR COUNTIES

Contract Time: 35 Working Days

DBE Goal Percent: 3.00

for constructing the Resurfacing and Traffic Stripe on CR-10 (Park Avenue) from east of the intersection of SR-25 (US-411) to the intersection of Kelly Creek Road and on Kelly Creek Road from the intersection of CR-10 (Park Avenue) to the I-20 Denied Access Line in Moody. Length 1.987 mi.

The Bracket Estimate on this project is from \$837,536 to \$1,023,655.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	17	SQYD	Removing Concrete Sidewalk
305B078	800	Ton	Crushed Aggregate, Section 825, Type B, For Miscellaneous Use
405A000	4,650	Gal	Tack Coat
407B000	2	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	31,600	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A361	3,200	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	100	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B651	3,850	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
618A000	15	SQYD	Concrete Sidewalk, 4" Thick
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 43,165.00)
701A231	5	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	5	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701B205	770	LF	Dotted, Class 2, Type A, Traffic Stripe
701C001	13	Mile	Solid Temporary Traffic Stripe
703A002	1,914	SQFT	Traffic Control Markings, Class 2, Type A
703B002	93	SQFT	Traffic Control Legends, Class 2, Type A
703D001	411	SQFT	Temporary Traffic Control Markings
705A030	24	Each	Pavement Markers, Class A-H, Type 2-C
705A032	266	Each	Pavement Markers, Class A-H, Type 1-B
705A037	305	Each	Pavement Markers, Class A-H, Type 2-D
705A038	133	Each	Pavement Markers, Class A-H, Type 2-E
740B000	359	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car