

**Alabama Department of Transportation
Proposal Item Summary**

032. STPNU-2419(250)

DALLAS COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Widening, Resurfacing, and Traffic Stripe on CR-52 from the junction of CR-63 to the Autauga County Line. Length 2.075 mi.

The Bracket Estimate on this project is from \$435,215 to \$531,929.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	640	LF	Removing Guardrail
210D021	400	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
401B108	23,342	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	2,335	Gal	Tack Coat
407B000	2	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A346	2,047	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	340	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B677	405	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
630A001	125	LF	Steel Beam Guardrail, Class A, Type 2
630A004	640	LF	Steel Beam Guardrail, Class B, Type 2
630C022	4	Each	Guardrail End Anchor, Type Special
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	390	CUYD	Topsoil
652A100	3	Acre	Seeding
656A010	3	Acre	Mulching
665F000	340	Each	Hay Bales
665J002	1,700	LF	Silt Fence
665O001	1,700	LF	Silt Fence Removal
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 23,400.00)
701A231	5	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C002	1	Mile	Broken Temporary Traffic Stripe (Paint)
701C003	8	Mile	Solid Temporary Traffic Stripe (Paint)
701G251	250	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A002	60	SQFT	Traffic Control Markings, Class 2, Type A
703D002	120	SQFT	Temporary Traffic Control Markings (Paint)
705A032	34	Each	Pavement Markers, Class A-H, Type 1-B
705A037	239	Each	Pavement Markers, Class A-H, Type 2-D
740B000	245	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car