

**Alabama Department of Transportation  
Proposal Item Summary**

**033. DPTA-5619(250)**

**RANDOLPH COUNTY**

Contract Time: 45 Working Days

DBE Goal Percent: 1.00

for constructing the Resurfacing (Full Depth Reclamation), Guardrail Installation, and Traffic Stripe on CR-87 from the junction of CR-438 to the intersection of SR-48 in Graham. Length 2.623 mi.

The Bracket Estimate on this project is from \$1,089,372 to \$1,331,454.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C010	33	SQYD	Removing Concrete Driveway
206D001	100	LF	Removing Guardrail
206E008	4	Each	Removing Guardrail End Anchor (All Type)
302A000	36,028	SQYD	Full Depth Reclamation, 8 inches thick
302B000	757	Ton	Portland Cement For Full Depth Reclamation
401A000	36,737	SQYD	Bituminous Treatment A
401B108	35,198	SQYD	Bituminous Treatment G (With Polymer Additive)
424A336	1,761	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range A/B
424B644	5,985	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	1,294	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A021	225	LF	Steel Beam Guardrail, Class A, Type 2 (Steel Post)
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
652A100	2	Acre	Seeding
656A010	2	Acre	Mulching
665F000	75	Each	Hay Bales
665J002	750	LF	Silt Fence
665O001	750	LF	Silt Fence Removal
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 58,200.00)
701A231	6	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	5	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	1	Mile	Broken Temporary Traffic Stripe
701C001	5	Mile	Solid Temporary Traffic Stripe
703A002	108	SQFT	Traffic Control Markings, Class 2, Type A
705A032	24	Each	Pavement Markers, Class A-H, Type 1-B
705A037	326	Each	Pavement Markers, Class A-H, Type 2-D
740B000	354	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740F002	12	Each	Barricades, Type III
740I002	8	Each	Warning Lights, Type B
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car