

**Alabama Department of Transportation
Proposal Item Summary**

046. 99-307-234-000-901

DALE COUNTY

Contract Time: 30 Working Days

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-53 (US-231) at the Rest Area (Drive and Parking Area) south of Ozark.

The Bracket Estimate on this project is from \$206,458 to \$252,338.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	1,356	Gal	Tack Coat
407B000	1	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	13,555	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A361	1,119	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
618C000	64	SQFT	Truncated Dome Retrofit
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 11,000.00)
701B207	75	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
703A002	1,396	SQFT	Traffic Control Markings, Class 2, Type A
703D001	1,037	SQFT	Temporary Traffic Control Markings
703H000	266	SQFT	Specialty Traffic Control Markings
705A030	12	Each	Pavement Markers, Class A-H, Type 2-C
740C000	128	SQFT	Special Construction Signs
740D000	15	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
742A001	2	Each	Portable Changeable Message Sign, Type 2