

**Alabama Department of Transportation
Proposal Item Summary**

047. 99-307-306-000-901

BARBOUR COUNTY

Contract Time: 30 Working Days

for constructing the Resurfacing and Traffic Markings on SR-1 (US-431) at the Rest Area (Parking Area) south of Eufaula.

The Bracket Estimate on this project is from \$202,344 to \$247,310.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	101	SQYD	Removing Concrete Sidewalk
206D003	75	LF	Removing Curb And Gutter
405A000	1,012	Gal	Tack Coat
407B000	1	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	10,116	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A361	835	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
614A000	25	CUYD	Slope Paving
618A000	65	SQYD	Concrete Sidewalk, 4" Thick
618C000	16	SQFT	Truncated Dome Retrofit
623C000	75	LF	Combination Curb & Gutter, Type C
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 10,500.00)
703A002	491	SQFT	Traffic Control Markings, Class 2, Type A
703D001	131	SQFT	Temporary Traffic Control Markings
703H000	697	SQFT	Specialty Traffic Control Markings
710A170	6	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)
710B001	16	LF	Roadway Sign Post (#3 "U" Channel Galvanized Steel)
740C000	128	SQFT	Special Construction Signs
740D000	15	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
742A001	2	Each	Portable Changeable Message Sign, Type 2