

Alabama Department of Transportation
Proposal Item Summary

016. HRRR-1519(250)

CLEBURNE COUNTY

Contract Time: 30 Working Days

for constructing the Safety Improvements (Guardrail Installation, Pavement Markers, Rumble Strip, Traffic Signs, and Traffic Stripe) on CR-24 from the Calhoun County Line to the junction of CR-3 in Abel. Length 2.358 mi.

The Bracket Estimate on this project is from \$149,699 to \$182,965.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
430B043	800	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A034	1,350	LF	Steel Beam Guardrail, Class A, Type 2 (8'-0" Post)
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
701A231	5	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701G251	500	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
705A032	36	Each	Pavement Markers, Class A-H, Type 1-B
705A037	274	Each	Pavement Markers, Class A-H, Type 2-D
705A039	175	Each	Pavement Markers, Class A-H, Type 2-A
710A160	16	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710A165	277	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background, Fluorescent)
710A170	19	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)
710B021	318	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
710C000	1	LS	Removal Of Existing Roadway Signs
740B000	141	SQFT	Construction Signs
740E000	25	Each	Cones (36 Inches High)
740M001	25	Each	Ballast For Cone
740O000	1	Each	Pilot Car