

**Alabama Department of Transportation
Proposal Item Summary**

018. HRRR-2419(251)

DALLAS COUNTY

Contract Time: 30 Working Days

for constructing the Guardrail Installations on CR-83 over Mulberry Creek (Site 1); on CR-74 over Soapstone Creek (Site 2); on CR-11 over Tatum Creek (Site 3); and on CR-29 over Dry Creek (Site 4). Length 0.505 mi.

The Bracket Estimate on this project is from \$197,407 to \$241,275.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	712	LF	Removing Guardrail
210D021	1,600	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
600A000	1	LS	Mobilization
630A001	50	LF	Steel Beam Guardrail, Class A, Type 2
630A004	712	LF	Steel Beam Guardrail, Class B, Type 2
630C022	16	Each	Guardrail End Anchor, Type Special
630C080	16	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	100	CUYD	Topsoil
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
665F000	320	Each	Hay Bales
665J002	1,650	LF	Silt Fence
665O001	1,650	LF	Silt Fence Removal
740B000	521	SQFT	Construction Signs
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone