

**Alabama Department of Transportation
Proposal Item Summary**

021. HRRR-3019(250)

FRANKLIN COUNTY

Contract Time: 30 Working Days

for constructing the Safety Improvements (Cross Slope Corrections, Guardrail Installation, Traffic Control Devices, and Traffic Stripe) on CR-12 (College Road) from the junction of SR-17 (US-43) to the junction of Dan Street in Phil Campbell. Length 2.773 mi.

The Bracket Estimate on this project is from \$287,128 to \$350,934.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$2.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
210D001	100	CUYD	Borrow Excavation (Loose Truckbed Measurement)
327D021	44	Ton	Plant Mix Bituminous Base, Widening, Mix 2
405A000	1,000	Gal	Tack Coat
424A340	230	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	6	Mile	Scoring Bituminous Pavement Surface
430B042	700	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type A)
600A000	1	LS	Mobilization
630A034	3,250	LF	Steel Beam Guardrail, Class A, Type 2 (8'-0" Post)
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 12,000.00)
701A030	6	Mile	Solid White, Class 2T, Type A Traffic Stripe
701A034	6	Mile	Solid Yellow, Class 2T, Type A Traffic Stripe
701C001	1	Mile	Solid Temporary Traffic Stripe
701G252	500	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
703A004	128	SQFT	Traffic Control Markings, Class 2T, Type A
703D001	128	SQFT	Temporary Traffic Control Markings
705A031	1,465	Each	Pavement Markers, Class A-H, Type 1-A
705A037	367	Each	Pavement Markers, Class A-H, Type 2-D
710A165	23	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background, Fluorescent)
710B021	26	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
740B000	250	SQFT	Construction Signs
740D000	60	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone